



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 26, 2009

SUBJECT: GENERAL DACEY TRAIL
Project TCSP-IL08(021)
Section 08-00048-00-BT (Shelbyville)
Shelby County
Contract No. 95582
Item 160
November 6, 2009 Letting
Addendum (B)

TO PROSPECTIVE BIDDERS:

Due to clarify information necessary to revise the following:

Proposal – Page 12 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.



Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Charles Ingersoll
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger
Engineer of Project Development
and Implementation



WorldTrail Stations (Typical Workout Stations)

www.playworldsystems.com

1-570-522-9800

FITNESS CENTER GENERAL NOTES:

1. Fitness Center workout stations are to be supplied and delivered to the project site by the City of Shelbyville. The Contractor will be required to install the workout stations, and furnish and install the gravel drainage system, workout station foundations, wood fiber surface material, geotextile fabric, curbing and foundations. Layout shall be as instructed by Field Engineer in an area approximately 50 feet x 50 feet.
2. There are fifteen (15) workout stations provided and are typically depicted as shown above. Each station shall be installed in concrete footings as per manufacturer instructions.
3. Above ground 8 inch curbing surrounding Fitness Center Area shall be black in color (Model Number 4850 – "GameTime" 1-800-235-2440 www.gametime.com, or approved equal), installed and anchored with concrete footings in accordance with manufacturer's instruction.
4. Engineered Wood Fiber surface shall be 8 inches in depth ("GTIMPAX FIBER" by "GameTime 1-800-235-2440 www.gametime.com, or approved equal). Fiber shall be installed over Geotextile Fabric ("GT Impax Geotextile Fabric by "GameTime" 1-800-235-2440 www.gametime.com, or approved equal).
5. Drainage system shall consist of 24inch wide by 3 inch deep gravel pockets on 6 foot centers. Longitudinal drains at a slope of 1% (min) and shall daylight outside fitness area. Geotextile fabric shall be placed above and below gravel pockets.
6. The contractor shall install the fitness center as outlined in the manufacturer's instructions and as directed by the Engineer.