

RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	08-00048-00-BT	SHELBY	27	8

** GENERAL DACEY TRAIL

BOLLARDS

STA	O/S	QUANTITY
410+39	C.L.	1.0 EACH
410+67	C.L.	1.0 EACH
	TOTAL	2.0 EACH

PAINT PAVEMENT LINE 6"

STA TO STA	OFFSET	COLOR	QUANTITY
410 + 40 TO 410+66	11' LEFT	WHITE	26 FOOT
410 + 40 TO 410+66	11' RIGHT	WHITE	26 FOOT
		TOTAL	52 FOOT

PAINT PAVEMENT LINE 24"

STA TO STA	OFFSET	COLOR	QUANTITY
410+40 TO 410+53	14' LEFT	WHITE	13 FOOT
		TOTAL	13 FOOT

SIDEWALK REMOVAL SCHEDULE

LOCATIONS	WIDTH	QUANTITY
STA 52+80 TO STA 55+00	4.0	888 SQ. FT.
STA 440+00 TO STA 442+75	4.0	1100 SQ. FT.
	TOTAL	1988 SQ. FT.

**PORTLAND CEMENT CONCRETE
SIDEWALK 5" SCHEDULE**

STA TO STA	WIDTH	SQ FT
STA 410+40 TO 410+38	10	20
STA 410+36 TO 410+26	10	100
STA 410+66 TO 410+68	10	20
STA 410+70 TO 410+80	10	100
STA 55+10 TO 55+14	8	32
	TOTAL	272

PIPE CULVERT SCHEDULE

SIZE	TYPE	LOCATION	LENGTH	METAL END SECTIONS
8"	1	433+00	32 FOOT	0
8"	1	435+20	32 FOOT	0
10"	1	1+98	32 FOOT	0
10"	1	401+00	24 FOOT	0
10"	1	410+28	24 FOOT	0
15"	1	410+95	32 FOOT	0
24"	2	419+61	38 FOOT	0
42"	2	405+80	36 FOOT	2

DETECTABLE WARNINGS

STA TO STA	WIDTH	SQ. FT.
410+38 TO 410+36	10	20
410+68 TO 410+70	10	20
	TOTAL	40 SQ. FT.

CITY OF SHELBYVILLE ILLINOIS
GENERAL DACEY TRAIL
PHASE 4