SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	947
	40600300	AGGREGATE (PRIME COAT)	TON	27
	40600990	TEMPORARY RAMP	SQ YD	62
	40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1644
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1146
	42400800	DETECTABLE WARNINGS	SQ FT	106
	44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1½"	SQ YD	13406
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	57
	44000600	SIDEWALK REMOVAL	SQ FT	884
	44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	503
	44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	15
	44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	84
	44213100	PAVEMENT FABRIC	SQ YD	99
	44213200	SAW CUTS	FOOT	3439
	44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	13066
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	57
	67100100	MOBILIZATION	L SUM	1
	70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1371
	70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	5979
	70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	862
	70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	120
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3001
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5979
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	862
*	78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	120
	Z0017202	DOWEL BARS 1 1/2 "	EACH	596
	Z0022800	FENCE REMOVAL	FOOT	38
	Z0075310	TIE BARS 3/4 "	EACH	66
	Z0075330	TIE BARS 1 1/4 "	EACH	596

* SPECIALTY ITEMS