

PAVING SCHEDULE

LOCATION	BIT MATL PR CT (GALLON)	AGGREGATE (PRIME COAT) (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N90, 2 1/4" (TON)
MARYVILLE ROAD			
STA. 201+62.69 TO STA. 226+76.49	946.6	27.0	1644.0
TOTAL	947	27	1644

TEMPORARY RAMP SCHEDULE

LOCATION	TEMPORARY RAMP (SQ YD)
MARYVILLE ROAD	
STA. 201+62.69	27
STA. 226+76.49	35
TOTAL	62

STRIPING SCHEDULE

LOCATION	TYPE	THERMOPLASTIC			PREFORMED PLASTIC
		4" YELLOW (FOOT)	4" WHITE (FOOT)	6" WHITE (FOOT)	12" WHITE (FOOT)
MARYVILLE ROAD					
STA. 201+62.69 TO STA. 226+76.49					
	STOP BAR				120
	CROSSWALK			805	
	DOUBLE CENTERLINE	4779			
	SKIP-DASH 10'-30'		1200		
	DIAGONALS			57	
TOTAL		4779	1200	862	120

CURB AND GUTTER SCHEDULE

LOCATION	C & G TYPE B-6.24 (FOOT)
MARYVILLE ROAD	
STA. 202+42.79 - 26.64' RT TO STA. 202+57.21 - 24.74' RT	15.00
STA. 210+70.41 - 24.12' RT TO STA. 210+82.61 - 24.01' RT	12.20
STA. 216+65.56 - 24.00' RT TO STA. 216+83.28 - 24.04' RT	17.72
STA. 223+72.54 - 23.87' RT TO STA. 223+85.04 - 23.87' RT	12.50
TOTAL	57

SIDEWALK SCHEDULE

LOCATION	P.C.C. SIDEWALK 4" (SQFT)
MARYVILLE ROAD	
STA. 201+81.54 - 35.54' LT TO STA. 201+89.87 - 34.75' LT	50.37
STA. 201+85.77 - 40.99' RT TO STA. 201+06.88 - 40.30' RT	44.00
STA. 202+29.39 - 38.35' RT TO STA. 202+35.40 - 35.40' RT	32.20
STA. 202+42.78 - 26.38' RT TO STA. 202+57.21 - 29.71' RT	64.36
STA. 202+45.15 - 30.53' LT TO STA. 202+57.68 - 30.05' LT	68.23
STA. 207+08.98 - 30.26' RT TO STA. 207+25.31 - 40.07' RT	120.41
STA. 207+64.61 - 35.08' RT TO STA. 207+79.76 - 30.38' RT	80.93
STA. 210+79.76 - 29.39' LT TO STA. 210+90.76 - 29.32' LT	55.00
STA. 214+66.25 - 29.39' LT TO STA. 214+86.35 - 38.55' LT	123.38
STA. 215+29.59 - 34.69' LT TO STA. 215+36.79 - 32.94' LT	26.63
STA. 216+76.18 - 29.65' LT TO STA. 216+81.68 - 29.65' LT	28.09
STA. 217+62.39 - 29.71' LT TO STA. 217+80.72 - 35.95' LT	116.14
STA. 218+29.88 - 38.30' LT TO STA. 218+47.37 - 30.06' LT	127.04
STA. 226+54.84 - 30.78' LT TO STA. 218+69.97 - 34.35' LT	71.27
STA. 226+50.61 - 30.16' RT TO STA. 226+72.61 - 30.13' RT	137.63
TOTAL	1146

4" PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKINGS, 4" "SKIP-DASH" (FOOT)	THERMOPLASTIC PAVEMENT MARKINGS, 4" "DOUBLE CENTERLINE" (FOOT)
MARYVILLE ROAD		
STA. 201+62.69 LT TO STA. 201+67.68 LT	5	
STA. 201+62.69 RT TO STA. 201+66.68 RT	5	
STA. 201+62.69 TO STA. 201+67.68		10
STA. 202+51.71 RT TO STA. 207+05.65 RT		
STA. 202+51.70 RT TO STA. 216+19.97 RT	344	
STA. 202+58.14 LT TO STA. 216+32.62 LT	342	
STA. 202+58.14 LT TO STA. 214+66.43 LT		
STA. 202+58.15 TO STA. 216+32.62		2750
STA. 207+82.96 RT TO STA. 216+32.63 RT		
STA. 215+69.07 LT TO STA. 216+32.63 LT		
STA. 216+38.63 RT TO STA. 226+47.48 RT		
STA. 216+38.63 RT TO STA. 226+47.48 RT	252	
STA. 216+38.63 TO STA. 226+47.46		2019
STA. 216+38.63 LT TO STA. 217+63.04 LT		
STA. 216+53.67 LT TO STA. 226+58.59 LT	252	
STA. 218+46.34 LT TO STA. 226+58.59 LT		
STA. 226+64.59 LT TO STA. 226+76.47 LT		
TOTAL	1200	4779

6" PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKINGS, 6" "CROSSWALK" (FOOT)	THERMOPLASTIC PAVEMENT MARKINGS, 6" "DIAGONALS" (FOOT)
MARYVILLE ROAD		
STA. 201+83.56 - 28.73' LT TO STA. 201+87.60 - 31.10' RT	60	
STA. 201+89.44 - 33.21' LT TO STA. 202+93.69 - 32.26' RT	66	
STA. 201+92.63 - 38.27' RT TO STA. 202+29.00 - 38.25' RT	36	
STA. 201+93.69 - 32.26' RT TO STA. 202+33.40 - 31.81' RT	40	
STA. 202+45.68 LT TO STA. 202+45.71 RT	48	
STA. 202+51.68 LT TO STA. 202+51.71 RT	48	
STA. 207+25.64 - 32.56' RT TO STA. 207+65.41 - 32.54' RT	40	
STA. 207+17.27 - 26.57' RT TO STA. 207+73.82 - 26.54' RT	57	
STA. 214+90.71 - 34.67' LT TO STA. 215+28.87 - 34.69' LT	38	
STA. 214+85.05 - 28.66' LT TO STA. 215+35.19 - 28.70' LT	50	
STA. 216+32.63 LT TO STA. 216+32.63 RT	48	57
STA. 216+38.63 LT TO STA. 216+38.63 LT	48	
STA. 217+80.51 - 30.58' LT TO STA. 218+28.78 - 30.59' LT	48	
STA. 217+66.62 - 24.57' LT TO STA. 218+42.35 - 24.59' LT	76	
STA. 226+58.59 LT TO STA. 226+58.61 RT	51	
STA. 226+64.59 LT TO STA. 226+64.61 RT	52	
TOTAL	805	57

12" PAVEMENT MARKING SCHEDULE

LOCATION	PRFM PLSTC PAVEMENT MARKINGS, 12" "STOP BAR" (FOOT)
MARYVILLE ROAD	
STA. 201+67.68	24
STA. 202+57.75	24
STA. 216+20.37	24
STA. 216+53.28	24
STA. 226+47.86	24
TOTAL	120