

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	PPS #	
				6-00688-0000	80% FED 20% STATE ROADWAY 0005
44200148	PAVEMENT PATCHING, TYPE III, 12 INCH	50 YD	100	100	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	6,628	6,628	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	304	304	
50105220	PIPE CULVERT REMOVAL	FOOT	514	514	
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	124	124	
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	382	382	
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	35	35	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	4	4	
54215550	METAL END SECTIONS 15"	EACH	14	14	
54215553	METAL END SECTIONS 18"	EACH	2	2	
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	210	210	⚠
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1	⚠
67100100	MOBILIZATION	L SUM	1	1	
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1	⚠
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	PPS #	
				6-00688-0000	80% FED 20% STATE ROADWAY 0005
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	13,539	13,539	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	108,788	108,788	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,504	1,504	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	108,788	108,788	
* 78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LETTERS AND SYMBOLS	SQ FT	122	122	
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	78	78	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	564	564	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	564	564	
<del>X0556100</del>	<del>PARTIAL-DEPTH PATCHING (SPECIAL)</del>	<del>SQ YD</del>	<del>1,150</del>	<del>1,150</del>	
X4060605	LEVELING BINDER (MACHINE METHOD), SPECIAL	TON	880	880	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	128,639	128,639	
X4406010	PARTIAL DEPTH REMOVAL, TYPE I, VARIABLE DEPTH	SQ YD	50	50	

\* SPECIALTY ITEM

⚠ REVISED 10-22-15

FILE NAME: p:\1084EBIDINTEC\illinois.gov\PI00T\...	USER NAME: sparkgo	DESIGNED: -	REVISED: -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE. 34	SECTION (1) RS-8	COUNTY MASON	TOTAL SHEETS 61	SHEET NO. 4
		CHECKED: -	REVISED: -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72H50		
		DATE: -	REVISED: -		ILLINOIS FED. AID PROJECT								
Default													