

SUMMARY OF QUANTITIES

COUNTY:	FRANKLIN CO	
ROUTE:	IL 149	
FUNDING:	80% FED / 20% STATE	80% FED / 20% CITY
LOCATION:	URBAN	URBAN
	ROADWAY	FACILITY
	0003	0028

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	URBAN ROADWAY	URBAN FACILITY
20100110	TREE REM OVAL (6 TO 15 UNITS DIAMETER)	UNIT	22	22	
20100210	TREE REM OVAL (OVER 15 UNITS DIAMETER)	UNIT	66	66	
20200100	EARTH EXCAVATION	CU YD	6,989	6,989	
20800150	TRENCH BACKFILL	CU YD	297	297	△
20900110	POROUS GRANULAR BACKFILL	CU YD	624	624	
* 25000100	SEEDING, CLASS 1	ACRE	1	1	
* 25000350	SEEDING, CLASS 7	ACRE	1	1	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	171	171	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	86	86	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	86	86	
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	2	2	
* 25100115	MULCH, METHOD 2	ACRE	2	2	

* SPECIALTY ITEM

△ REV. 10-21-2020

REV. - MS

MODEL: Default
FILE NAME: P:\p1\p1room.dwt
PROJECT: 78481\CAD\DATA\CAD\sheet\78481_sht-cr_501_index.dgn

USER NAME = maesbl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
PLOT SCALE = 100.0000' / in.	DRAWN -	REVISED -			873	28-5106(W-3,RS-8)	FRANKLIN	171	6	
PLOT DATE = 8/14/2020	CHECKED -	REVISED -			CONTRACT NO. 78481					
	DATE -	REVISED -			SCALE: SHEET OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES - CONT

COUNTY:	FRANKLIN CO	
ROUTE:	IL 149	
FUNDING:	80% FED / 20% STATE	80% FED / 20% CITY
LOCATION:	URBAN	URBAN
TOTAL QUANTITY	ROADWAY 0003	FACILITY 0028

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0003	FACILITY 0028
44003100	MEDIAN REMOVAL	SQ FT	488	488	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1,150	1,150	
5080205	REINFORCEMENT BARS, EPOXY COATED	POUND	226	226	
52200900	CONCRETE STRUCTURES (RETAINING WALL)	CU YD	105	105	
54248510	CONCRETE COLLAR	CU YD	1	1	
550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FOOT	143	143	
550B0380	STORM SEWERS, CLASS B, TYPE 2 18"	FOOT	175	175	
550B0400	STORM SEWERS, CLASS B, TYPE 2 21"	FOOT	375	375	
550B0410	STORM SEWERS, CLASS B, TYPE 2 24"	FOOT	262	262	
550B0420	STORM SEWERS, CLASS B, TYPE 2 27"	FOOT	289	289	⚠
550B0430	STORM SEWERS, CLASS B, TYPE 2 30"	FOOT	527	527	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	3	3	
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1	1	

⚠ REV. 10-21-2020

REV. - MS

MODEL: Default
FILE NAME: p:\ip\arccon\dot\illinois\gov-p\WIDOT\Documents\DOT Offices\District 9\Projects\78481\CAD\Drawings\CAD\Drawings\78481_sta-cv_ssq_index.dgn

USER NAME = maesbl	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 100.0000' / in.	CHECKED -	REVISED -
PLOT DATE = 8/14/2020	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
873	28-5106(W-3,RS-8)	FRANKLIN	171	9
CONTRACT NO. 78481				
ILLINOIS FED. AID PROJECT				

STORM SEWER SCHEDULE

LOCATION							STORM SEWER. CLASS B, TYPE 2						CONCRETE COLLAR CU YD	TRENCH BACKFILL CU YD
							15" DIA. FOOT	18" DIA. FOOT	21" DIA. FOOT	24" DIA. FOOT	27" DIA. FOOT	30" DIA. FOOT		
STATION	OFFSET	TO	STATION	OFFSET	ALIGNMENT									
712+06	30.1	LT TO	712+10	19.9	LT	IL 149E					11		3	
712+10	19.9	LT TO	712+64	20.0	LT	IL 149E			53				11	
712+64	20.0	LT TO	713+85	20.2	LT	IL 149E			122				24	
713+85	20.2	LT TO	714+79	19.8	LT	IL 149E			94				16	
714+79	19.8	LT TO	715+96	19.7	LT	IL 149E			118				20	
715+96	19.7	LT TO	716+46	19.7	LT	IL 149E		50					8	
716+46	19.7	LT TO	716+95	19.8	LT	IL 149E		49					8	
716+95	19.8	LT TO	718+38	20.1	LT	IL 149E	143						19	
722+30	24.5	LT TO	722+35	27.3	LT	IL 149E			5				1	
712+33	28.6	RT TO	712+30	20.0	RT	IL 149E					9		3	
712+34	36.1	RT TO	712+33	28.6	RT	IL 149E					7		2	
712+30	20.0	RT TO	713+24	19.8	RT	IL 149E					95		23	
713+16	37.5	RT TO	713+25	28.7	RT	IL 149E					13		4	
713+24	19.8	RT TO	713+75	19.9	RT	IL 149E					51		12	
713+75	19.9	RT TO	714+26	20.0	RT	IL 149E					52		13	
714+26	35.6	RT TO	714+28	19.8	RT	IL 149E			16			0.44	4	
714+26	20.0	RT TO	714+80	19.8	RT	IL 149E					54		13	
714+80	29.0	RT TO	714+80	19.8	RT	IL 149E			9			0.44	1	
714+80	19.8	RT TO	717+14	19.8	RT	IL 149E					235		55	
717+14	38.1	RT TO	717+15	29.6	RT	IL 149E			8				2	
717+14	19.8	RT TO	718+69	20.0	RT	IL 149E			155				27	
718+69	20.0	RT TO	719+37	17.9	RT	IL 149E		68					11	
719+37	22.5	RT TO	719+37	17.9	RT	IL 149E		5					1	
719+40	25.4	RT TO	719+37	22.5	RT	IL 149E		3					1	
722+34	28.5	RT TO	722+38	16.1	RT	IL 149E				12			3	
725+69	28.3	RT TO	725+74	15.9	RT	IL 149E				13			3	
729+03	25.6	RT TO	729+10	16.5	RT	IL 149E				11			3	
729+44	28.4	RT TO	729+39	16.5	RT	IL 149E				11			3	
732+41	28.1	RT TO	732+45	17.7	RT	IL 149E				10			2	
TOTAL							143	175	375	262	0	527	0.88	297

MODEL: S:\schedules\...
 FILE NAME: ...
 PROJECT: 78481\...
 USER: maestl

△ REV. 10-21-2020

USER NAME = maestl DRAWN - PLOT SCALE = 100,0000' / in. PLOT DATE = 10/21/2020	DESIGNED - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	STORM SEWER SCHEDULE	SCALE: SHEET OF SHEETS STA. TO STA.	F.A.P. RTE. SECTION COUNTY TOTAL SHEETS SHEET NO. 873 28-5106(W-3,RS-8) FRANKLIN 171 22 CONTRACT NO. 78481
ILLINOIS FED. AID PROJECT						

