



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 28, 2020

SUBJECT: Route FAU 6594 & FAP 671 (Western Ave. & IL 8)  
Section 16-00368-01-PV (City of Peoria)  
Peoria County  
Contract No. 89766  
Item 099  
November 6, 2020 Letting  
Addendum B

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

### **1. Revised pages 56 – 58 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

installation of the soldier piles shall be in accordance with the provisions in Article 522 of the Standard Specifications, with exceptions and additional work items as noted herein.

The remainder of the retaining wall components, as shown on the plans, such as furnishing soldier piles, timber lagging, concrete facing, shear studs, reinforcement bars, railing, and various drainage items, etc. are not included in this Special Provision but are paid for as specified elsewhere in this Contract.

he proximity of the proposed soldier pile retaining walls to existing structures causes concern about the possibility of damage to the existing structures during construction activities. The Contractor shall exercise care during all construction activities and shall utilize appropriate methods of construction to protect properties near the proposed construction limits from damage due to demolition and construction activities.

The Contractor shall determine the most appropriate method of installation of the soldier piles to avoid damage to the adjacent existing structures. The Contractor has the option of drilling for the installation of the soldier piles per Article 522.08(b) (1) of the Standard Specifications. All provisions in Article 522 of the Standard Specifications apply for the installation of the soldier piles with the exception of 522.08 (b) (2) where only a vibratory hammer will be allowed to install the piles.

[Intentionally blank]

[Intentionally blank]

[Intentionally blank]

**Basis of Payment.** All materials, labor, and equipment necessary to perform the work as specified herein and as directed by the Engineer will be included in the contract unit price per Foot for DRIVING SOLDIER PILES.

**STORM SEWER, (WATER MAIN QUALITY PIPE)**

Effective January 1, 2011

Revised August 1, 2014

This work consists of constructing storm sewer to meet water main standards, as required by the IEPA or when otherwise specified. The work shall be performed in accordance with applicable parts of Section 550 of the Standard Specifications, applicable sections of the current edition of the IEPA Regulations (Title 35 of the Illinois Administrative Code, Subtitle F, Chapter II, Section 653.119), the applicable sections of the current edition of the "Standard Specifications for Water and Sewer Main Construction in Illinois", and as herein specified.

This provision shall govern the installation of all storm sewers which do not meet IEPA criteria for separation distance between storm sewers and water mains. Separation criteria for storm sewers placed adjacent to water mains and water service lines are as follows: