

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAI Routes 55 & 72
D6 OVD SIN STR REPL 2009-11
Sangamon County
Sheet 4 of 32
Contract Number 46010

Schedule of Overhead Sign Structure Replacement

Location No.:	6-01	State I.D. No.:	6C084I055L107.2				
County:	Sangamon	Route:	I-55	M.P.:	107.2	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1.00					
OVERHEAD SIGN STRUCTURE-CANTILEVER TYPE II-C-A	FOOT	30.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	0.20					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	1.00					
REMOVE SIGN PANEL - TYPE 3	SQ FT	97.50					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL - TYPE 3	SQ FT	97.50					
OVERHEAD SIGN STRUCTURE WALKWAY (SPECIAL)	FOOT	15.00					
This structure is being completely replaced.							
This work will be completed during District 6 night time hours.							

Location No.:	6-02	State I.D. No.:	6S084I055R081.7				
County:	Sangamon	Route:	I-55	M.P.:	81.7	Direction:	NB
Description of Work	Unit	Quantity					
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A	FOOT	116.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	24.60					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
SIGN PANEL - TYPE 3	SQ FT	241.50					
RE-ERECT OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	46.00					
This structure is being completely replaced.							
This work will be completed during District 6 night time hours.							

Location No.:	6-03	State I.D. No.:	6S084I055R090.1				
County:	Sangamon	Route:	I-55	M.P.:	90.1	Direction:	NB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE III-A	FOOT	110.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	22.00					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	581.00					
REMOVE & REINSTALL WALKWAY	FOOT	64.00					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	3.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
This structure is being completely replaced.							
This work will be completed during District 6 night time hours.							

Location No.:	6-04	State I.D. No.:	6S084I055L099.8				
County:	Sangamon	Route:	I-55	M.P.:	99.8	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE III-A	FOOT	109.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	22.00					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	609.00					
REMOVE & REINSTALL WALKWAY	FOOT	59.50					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	3.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	4.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
This structure is being completely replaced.							
This work will be completed during District 6 night time hours.							

Location No.:	6-05	State I.D. No.:	6S084I055L090.5				
County:	Sangamon	Route:	I-55	M.P.:	90.5	Direction:	SB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE II-A	FOOT	108.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	26.50					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	319.00					
REMOVE & REINSTALL WALKWAY	FOOT	51.00					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	2.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	2.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
IMPACT ATTENUATOR REMOVAL	EACH	1.00					
IMPACT ATTN NRD TL3	EACH	1.00					
ATTENUATOR BASE	SQ YD	51.60					
This structure is being completely replaced.							
This work will be completed during District 6 night time hours.							

Location No.:	6-06	State I.D. No.:	6S084I072R097.0				
County:	Sangamon	Route:	I-72	M.P.:	97	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN TYPE III-A	FOOT	113.00					
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE	EACH	2.00					
DRILLED SHAFT CONCRETE FOUNDATION	CU YD	22.00					
REMOVE CONCRETE FOUNDATION OVERHEAD	EACH	2.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	555.00					
REMOVE & REINSTALL WALKWAY	FOOT	58.00					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	3.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	2.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
This structure is being completely replaced.							
This work will be completed during District 6 night time hours.							

Location No.:	6-07	State I.D. No.:	6C084I072R103.6				
County:	Sangamon	Route:	I-72	M.P.:	103.6	Direction:	EB
Description of Work	Unit	Quantity					
REPAIR CONCRETE FOUNDATION FOR OVERHEAD SIGN STRUCTURE	EACH	1.00					
TIGHTEN CANTILEVER CONNECTION	EACH	2.00					
REPLACE / TIGHTEN CLIP PER SIGN	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	3.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					