

PROJECT: GATEWAYS AND CORNER GARDENS AT 87TH STREET
 COOK COUNTY / CITY OF CHICAGO

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2005-069 LS	COOK	60	4
STA. 1255+15 (SB I-94)		TO STA. 1263+40 (SB I-94)		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

60A75

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	100% STATE		100% CITY OF CHICAGO
				DAN RYAN Y003	DAN RYAN Y007	DAN RYAN Y003
20200100	EARTH EXCAVATION	CU YD	20	20		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	94	89		5
21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	604	604		
21101825	COMPOST FURNISH AND PLACE, 6"	SQ YD	604	604		
25000210	SEEDING, CLASS 2A	ACRE	0.50	0.50		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	67	67		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	59	59		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	54	54		
25100630	EROSION CONTROL BLANKET	SQ YD	1668	1668		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	37	37		
28000510	INLET FILTERS	EACH	14	14		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3			3
42001300	PROTECTIVE COAT	SQ YD	110			110
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	373			373
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	26			26
44000300	CURB REMOVAL	FOOT	10			10
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	146			146
44000600	SIDEWALK REMOVAL	SQ FT	418			418
44004250	PAVED SHOULDER REMOVAL	SQ YD	26			26
50200100	STRUCTURE EXCAVATION	CU YD	75	67		8
50300225	CONCRETE STRUCTURES	CU YD	20	20		
50300300	PROTECTIVE COAT	SQ YD	30	30		
50300510	RUSTICATION FINISH	SQ FT	56	56		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2670	2670		
56104600	WATER VALVES 2"	EACH	2			2
56200900	WATER SERVICE LINE 2 1/2"	FOOT	229			229
60600605	CONCRETE CURB, TYPE B	FOOT	38.0	28.0		10.0
66410300	CHAIN LINK FENCE REMOVAL	FOOT	33	33		
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	315	315		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
▲ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	98			98
▲ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	24			24
▲ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	220			220

▲ - Specialty Items

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
 SHEET 1 OF 2

SCALE: NONE
 DATE: JUNE 20, 2008

DRAWN BY: JDF
 CHECKED BY: RTM

Rev.