

PROJECT: GATEWAYS AND CORNER GARDENS AT 79TH STREET  
 COOK COUNTY / CITY OF CHICAGO

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	2005-070 LS	COOK	65	5
STA. 2308+17 (NB I-94) TO STA. 2316+90 (NB I-94)		ILLINOIS FED. AID PROJECT		
STA. 1308+46 (SB I-94) TO STA. 1318+61 (SB I-94)				

60A76

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL	SEQ 01	SEQ 02
				100% STATE DAN RYAN Y003	100% STATE DAN RYAN Y003
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	66		66
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	23		23
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	233		233
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	28		28
81400200	HEAVY-DUTY HANDHOLE	EACH	3		3
X0326143	FLUTED KNEE WALL (SPECIAL)	FOOT	25	25	
K1003460	LANDSCAPE MAINTENANCE	CAL MO	11	11	
X0326144	TACTILE/DETECTABLE WARNING SURFACE	SQ FT	32		32
A2012003	TREE, AESCULUS X CARNEA 'FORT MCNAIR' (FORT MCNAIR RED HORSECHESTNUT), 3" CALIPER, MATCHING HEADS	EACH	10	10	
B2004568	TREE, MALUS RED PEACOCK (RED PEACOCK CRABAPPLE), 2-1/2" CALIPER, MATCHING HEADS	EACH	7	7	
X0326145	WATER SERVICE LINE 3" (SPECIAL)	FOOT	15		15
C2010930	SHRUB, SYRINGA MEYERI PALIBIN (DWARF KOREAN LILAC), 2-1/2' HEIGHT, BALLED AND BURLAPPED	EACH	440	440	
K0030400	PERENNIAL PLANTS, DAYLILIES	UNIT	13	13	
K0030470	PERENNIAL PLANT, ORNAMENTAL GRASS TYPE	UNIT	22	22	
X0301407	PERENNIAL PLANTS, GALI ON POT	UNIT	19	19	
X0320870	BRACED EXCAVATION	CU YD	10		10
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103	
X0325604	WEED CONTROL, PRE-EMERGENT HERBICIDE	GALLON	1	1	
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	404	404	
X0324525	PLANTING MIX FURNISH AND PLACE 36"	SQ YD	15	15	
X0325102	INSPECTION PIPE 4 INCH	EACH	3		3
X0325103	WATER METER IN VAULT, 2 INCH	EACH	2		2
X0325104	WATER TAP, 2 INCH	EACH	2		2
X0325105	IRRIGATION SYSTEM	SQ YD	858		858
X0325106	IRRIGATION SYSTEMS FALL SHUTDOWN	EACH	2		2
X0325107	IRRIGATION SYSTEMS SPRING STARTUP	EACH	2		2
X0325108	BACKFLOW PREVENTER (RPZ), 2 INCH	EACH	2		2
X0325109	POROUS GRANULAR MATERIAL	CU YD	6		6
X0656300	PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	108		108
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	69		69
X0325970	SOIL CONDITIONER 3"	SQ YD	1588	1588	
XX104800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12	FOOT	127		127
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0027800	GEOTECHNICAL FABRIC	SQ YD	28	28	

\* - SPECIALTY ITEM

TYLIN INTERNATIONAL

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.I. 94 (DAN RYAN EXPRESSWAY)  
 SUMMARY OF QUANTITIES  
 SHEET 2 OF 2  
 SCALE: NONE  
 DATE: MAY 1, 2008  
 DRAWN BY: JDF  
 CHECKED BY: JPM

4/30/2008 9:26:03 AM P:\02\3\Road\022E\sq22E\02\3.dgn