

SUMMARY OF QUANTITIES

| CODE NO. | ITEM | UNIT | URBAN 100% STATE QUANTITY | ROADWAY | | LANDSCAPING Y003 | CODE NO. | ITEM | UNIT | URBAN 100% STATE QUANTITY | ROADWAY | | LANDSCAPING Y003 |
|---------------------|--|-------------------|---------------------------------|---------------|--------------|---------------------|---------------------|---|------------------|---------------------------------|--------------|--------------|---------------------|
| | | | | IDOT J000 | CDOT J000 | | | | | | IDOT J000 | CDOT J000 | |
| 25000210 | SEEDING, CLASS 2A | ACRE | 0.25 | 0.25 | | | X0325105 | IRRIGATION SYSTEM | SO YD | 8.44 | | 8.44 | |
| 25000400 | NITROGEN FERTILIZER NUTRIENT | POUND | 55 | 23 | | 32 | X0325106 | IRRIGATION SYSTEM FALL SHUT-DOWN | EACH | 3 | | 3 | |
| 25000500 | PHOSPHORUS FERTILIZER NUTRIENT | POUND | 42 | 23 | | 19 | X0325107 | IRRIGATION SYSTEM SPRING START-UP | EACH | 3 | | 3 | |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT | POUND | 36 | 23 | | 13 | X0325108 | BACKFLOW PREVENTER (RPZ), 2 INCH | EACH | 3 | | 3 | |
| 25100630 | EROSION CONTROL BLANKET | SQ YD | 1222 | 1222 | | | X6065740 | CONCRETE MEDIAN SURFACE, 5" (MODIFIED) | SQ FT | 152 | | 152 | |
| 28000510 | INLET FILTERS | EACH | 14 | 14 | | | X7011015 | TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS) | LSUM | 1 | 1 | | |
| 31101200 | SUB-BASE GRANULAR MATERIAL, TYPE B 4" | SQ YD | 5 | | 5 | | XX006326 | TYPE K COPPER PIPE 2" | FOOT | 150 | | 150 | |
| 42001300 | PROTECTIVE COAT | SQ YD | 107 | | 107 | | XX104800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-V.12 | FOOT | 15 | | 15 | |
| 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | SQ YD | 5 | | 5 | | XX152400 | SAND CUSHION, 3 INCH | CU YD | 2.6 | | 2.6 | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 273 | | 273 | | Z0013798 | CONSTRUCTION LAYOUT | LSUM | 1 | 1 | | |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL | SQ YD | 5 | | 5 | | Z0076600 | TRAINEES | HOURL | | | | |
| 44000300 | CURB REMOVAL | FOOT | 18 | | 18 | | A2002012 | TREE, AESCULUS FLAVA (YELLOW SWEET BUCKEYE), 3" CALIPER, BALLED AND BURLAPPED | EACH | 13 | | | 13 |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL | FOOT | 30 | | 30 | | X0326146 | SOIL CONDITIONER | SQ YD | 1714 | | | 1714 |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 273 | | 273 | | K1003460 | LANDSCAPE MAINTENANCE | CAL MO | 12 | | | 12 |
| 44003100 | MEDIAN REMOVAL | SQ FT | 152 | | 152 | | C2C06026 | SHRUB, RHUS TYPHINA 'TIGER EYES', (TIGER EYES CUTLEAF STAGHORN SUMAC), 24" HEIGHT, CONTAINER | EACH | 522 | | | 522 |
| 44201357 | CLASS C PATCHES, TYPE III, 10 INCH | SQ YD | 45 | | 45 | | | | | | | | |
| 56104600 | WATER VALVES 2" | EACH | 3 | | 3 | | | | | | | | |
| 60601005 | CONCRETE CURB, TYPE B (SPECIAL) | FOOT | 18 | | 18 | | | | | | | | |
| 60604100 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (MODIFIED) | FOOT | 15 | | 15 | | | | | | | | |
| 67100100 | MOBILIZATION | LSUM | 1 | 1 | | | | | | | | | |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | LSUM | 1 | 1 | | | | | | | | | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 12 | 12 | | | | | | | | | |
| 67000500 | ENGINEER'S FIELD OFFICE, TYPE B | CAL MO | 16 | 16 | | | | | | | | | |
| B2006120 | TREE, SYRINGA PEKINENSIS MORTON (CHINA SNOW PEKING LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED | EACH | 11 | | | 11 | | | | | | | |
| K0030400 | PERENNIAL PLANTS, DAYLILIES | UNIT | 13.30 | | | 13.30 | | | | | | | |
| K0030470 | PERENNIAL PLANTS, ORNAMENTAL GRASS TYPE | UNIT | 16.50 | | | 16.50 | | | | | | | |
| X0301407 | PERENNIAL PLANTS, GALLON POT | UNIT | 20.92 | | | 20.92 | | | | | | | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 52 | 52 | | | | | | | | | |
| X0325604 | WEED CONTROL, PRE-EMERGENT HERBICIDE | GALLON | 1 | | | 1 | | | | | | | |
| X0325103 | WATER METER IN VAULT, 2 INCH | EACH | 3 | | 3 | | | | | | | | |
| X0325104 | WATER TAP, 2 INCH | EACH | 3 | | 3 | | | | | | | | |

• DENOTES SPECIALTY ITEMS

CTE | AECOM

Rev. SOQ-1

| REVISIONS | | ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. 90/94 (DAN RYAN EXPRESSWAY) 63RD STREET GATEWAY LANDSCAPING AND IRRIGATION |
|-----------|------|---|
| NAME | DATE | |
| | | SUMMARY OF QUANTITIES |
| | | |
| | | |
| | | |
| | | |

SCALE: NONE
DATE: MAY 02, 2008

DRAWN BY: RMG
CHECKED BY: JAL