

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
876	9Y-RS-7	WILL	100	42
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

CONTRACT NO. 60E52

1 PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.  
WITH GRATING FOR CONC. FES, 600 mm  
STA. 1+267.775, 9.48m RT  
INV. 231.089

8 CB, 1.2m, TY A, W/ TY8 GRATE  
STA. 1+396.830, 9.112 RT  
T.G. 233.000  
INV. 231.857 (N)  
INV. 231.761 (S)

15 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 1+730.604, 9.483m LT  
INV. 232.000

22 PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.  
WITH GRATING FOR CONC. FES, 600 mm  
STA. 2+008.230, 9.000m RT  
INV. 228.379

2 CB, 1.5m, TY A, W/ TY8 GRATE  
STA. 1+279.60, 9.542 RT  
T.G. 232.189  
INV. 231.140 (N)  
INV. 231.150 (S)

9 CB, 1.2m, TY A, W/ TY8 GRATE  
STA. 1+436.526, 8.955 RT  
T.G. 233.445  
INV. 232.046 (N)  
INV. 232.052 (S)

16 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 1+742.240, 25.314m LT  
INV. 230.450

23 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 2+056.180, 8.992m LT  
INV. 226.732

3 CB, 1.5m, TY A, W/ TY8 GRATE  
STA. 1+296.54, 9.592 RT  
T.G. 232.360  
INV. 231.198 (N)  
INV. 231.220 (S)

10 CB, 1.2m, TY A, W/ TY8 GRATE  
STA. 1+459.557, 9.105 RT  
T.G. 233.430  
INV. 232.172 (N)  
INV. 232.171 (S)

17 PRECAST REIN. CONC. FLARED END SECTION, 450 mm DIA.  
WITH GRATING FOR CONC. FES, 450 mm  
STA. 1+798.632, 9.060m RT  
INV. 229.961

24 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 2+066.332, 8.993m LT  
INV. 226.585

4 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 1+267.775, 9.48m LT  
INV. \_\_\_\_\_

11 CB, 1.2m, TY A, W/ TY8 GRATE  
STA. 1+482.711, 10.625 RT  
T.G. 233.275  
INV. 232.298 (N)  
INV. 232.402 (S)

18 PRECAST REIN. CONC. FLARED END SECTION, 450 mm DIA.  
WITH GRATING FOR CONC. FES, 450 mm  
STA. 1+799.182, 8.960m LT  
INV. 230.101

25 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 2+450  
INV. 221.453

5 CB, 1.5m, TY A, W/ TY8 GRATE  
STA. 1+316.694, 9.410 RT  
T.G. 232.576  
INV. 231.274 (N)  
INV. 231.533 (S)

12 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 1+489.714, 9.302m RT  
INV. \_\_\_\_\_

19 PRECAST REIN. CONC. FLARED END SECTION, 450 mm DIA.  
WITH GRATING FOR CONC. FES, 450 mm  
STA. 1+859.700, 8.108m LT  
INV. 231.691

26 CB, 1.5 m, TY A, W/ TY8 GRATE  
STA. 2+500  
INV. 220.075 (N)  
INV. 219.875 (S)

6 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 1+332.500, 9.302m LT  
INV. \_\_\_\_\_

13 PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.  
WITH GRATING FOR CONC. FES, 600 mm  
STA. 1+732.540, 13.738m LT  
INV. 230.581

20 PRECAST REIN. CONC. FLARED END SECTION, 450 mm DIA.  
WITH GRATING FOR CONC. FES, 450 mm  
STA. 1+878.330, 8.117m LT  
INV. 231.759

27 PRECAST REIN. CONC. FLARED END SECTION, 375 mm DIA.  
WITH GRATING FOR CONC. FES, 375 mm  
STA. 2+542  
INV. 218.497

7 CB, 1.2m, TY A, W/ TY8 GRATE  
STA. 1+359.840, 9.302 RT  
T.G. 233.125  
INV. 231.743 (N)  
INV. 231.749 (S)

14 PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.  
WITH GRATING FOR CONC. FES, 600 mm  
STA. 1+736.730, 12.480m RT  
INV. 230.401

21 PRECAST REIN. CONC. FLARED END SECTION, 600 mm DIA.  
WITH GRATING FOR CONC. FES, 600 mm  
STA. 1+997.940, 9.000m RT  
INV. 228.639

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p style="text-align: center;"><b>IL. ROUTE 1 DRAINAGE STRUCTURE TABLE</b></p> <p>SCALE: NONE                      DRAWN BY HMO</p> <p>DATE: 9/5/2008                      CHECKED BY R.K.</p>