

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
F.A.P. 324	23B (1&2)F	McHENRY	17	2
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT-		

Contract # 60E54

GENERAL NOTES

- For structural steel notes, see Sheet 15 of 17.
- Fasteners shall be AASHTO M164 Type 1, mechanically galvanized bolts. Bolts  $\frac{7}{8}$  in. dia., holes  $\frac{15}{16}$  in. dia., unless otherwise noted.
- Calculated weight of Structural Steel = 468.200 pounds (Gr. 50), 22,370 pounds (Gr. 36).
- Bearing seat surfaces shall be constructed or adjusted to the designated elevations within a tolerance of  $\frac{1}{8}$  in. (0.01 ft.). Adjustment shall be made either by grinding the surface or by shimming the bearings.
- The Organic Zinc Rich Primer / Epoxy / Urethane Paint System shall be used for painting of new structural steel except where otherwise noted. The entire system shall be shop applied, with the exception that masked off connection surfaces, field installed fasteners and damaged areas shall be touched up in the field. The color of the final finish coat for all interior steel surfaces shall be Gray, Munsell No. 5B 7/1. The color of the final finish coat for the exterior and bottom flange of the fascia beams shall be Blue, Munsell No. 10B 3/6. See Special Provision for "Cleaning and Painting New Metal Structures".

INDEX OF SHEETS

1	TITLE SHEET
2	INDEX OF SHEETS, GENERAL NOTES & SUMMARY OF QUANTITIES
3	GENERAL PLAN
4	GENERAL DATA
* 5-8	TOP OF SLAB ELEVATIONS
* 9-10	TOP OF APPROACH SLAB ELEVATIONS
* 11-13	SUPERSTRUCTURE
14	FRAMING PLAN
15	FRAMING DETAILS
* 16	ABUTMENTS
* 17	PIERS

\* These drawings included in fabrication contract for information only.

SUMMARY OF QUANTITIES

URBAN  
SET-Y-2A  
100% STATE

Code No.	Item	Unit	Total
50500205	Furnishing Structural Steel	L Sum	1
50500455	Storage of Structural Steel	Cal Dq'	60

BEAM AND BEARING FABRICATION

INDEX OF SHEETS, GENERAL NOTES  
& SUMMARY OF QUANTITIES

ILL. ROUTE 23 OVER  
KISHWAUKEE RIVER  
F.A.P. RT. 324 - SEC. 23B (1&2)F  
MCHENRY COUNTY  
STATION 69+02.50  
STRUCTURE NO. 056-0001

DESIGNED	CJB
CHECKED	PWO
DRAWN	DRP
CHECKED	PJM



V3 Companies of Illinois Ltd.  
7325 Janes Avenue  
Woodridge, IL 60517  
630.724.9200 phone  
630.724.9202 fax  
www.v3co.com

Rev. 10-20-08