SUMMARY OF QUANTITIES

	CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 0000					
	X6021900	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE, RESTIRCTOR PLATE	EACH	1	1					
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	96	96					
	20101000	TEMPORARY FENCE	FOOT	1037	1037					
	20200100	EARTH EXCAVATION	CU YD	6403	6403					
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1201	1201					
*	25000210	SEEDING, CLASS 2A	ACRE	0.80	0.80					
*	25000310	SEEDING, CLASS 4	ACRE	1.75	1.75					
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	72	72					
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	72	72					
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	72	72					
*	25100630	EROSION CONTROL BLANKET	SQ YD	12,342	12,342					
	28100105	STONE RIPRAP, CLASS A3	SQ YD	10	10					
	28200200	FILTER FABRIC	SQ YD	10	10					
	54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	2	2					
	54247150	GRATING FOR CONCRETE FLARED END SECTION 30"	EACH	2	2					
	550A0140	STORM SEWERS, CLASS A, TYPE 1 30"	FOOT	35	35					
	66400505	CHAIN LINK FENCE, 8'	FOOT	128	128					
	66410300	CHAIN LINK FENCE REMOVAL	FOOT	128	128					
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1016	1016					
*	66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1					
	67100100	MOBILIZATION	L SUM	1	1					
*	K0038000	PERENNIAL PLANTS, WETLAND EMERGENT TYPE	UNIT	28	28					
	X0300894	PIPE CULVERT REMOVAL 18"	FOOT	60	60					
	X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	139	139					
	X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	2	2					
	X2800110	TEMPORARY DITCH CHECKS, AGGREGATE	EACH	3	3					
	XX000714	FENCE TO BE REMOVED AND RE-ERECTED	FOOT	85	85					
	X6640200	TEMPORARY CHAIN LINK FENCE	FOOT	250	250					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE FEDERAL 100%	BRIDGE SN 016 0065				

* Specialty Items

FILE NAME =	USER NAME = lajsd	DESIGNED -	REVISED -
K:\p99107\L438\IL19\sh_oil.dgn		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 8/27/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

NORTHSIDE MAINTENANCE YARD
IL. RTE. 43 (HARLEM AVENUE) & IL. RTE. 19 (IRVING PARK ROAD)
SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	2008-036 LS	COOK		3

CONTRACT NO. 60E77

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT