


- 12' SECTION OF GUARDRAIL LOCATE AT ALL NON-SPLICE MOUNTING POINTS

GALVANIZED STEEL PLATE  $-1\frac{7}{4}$ "  $\times$  3"  $\times$   $\frac{1}{8}$ " AT ALL POST MOUNTING BOLTS

NOTE:

DIAMOND TIPPED DRILL SHALL BE USED TO DRILL THRU REINFORCEMENT BARS



## NOTE:

POSTS SHALL BE HOT DIPPED GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM DESIGNATIONS A-123 AND A-385.

TWO PERCENT (2%) OF ALL ANCHOR BOLTS SHALL BE TEST LOADED IN PLACE. MIN. TEST LOAD = 8 KIPS.

ALL BOLTS, NUTS AND WASHERS SHALL BE GALVANIZED IN ACCORDANCE WITH ASTM DESIGNATION A-153.

FOR MATERIAL COMPOSITION OF PREFABRICATED PAD, SEE ARTICLE 54.9(F), (BEARING AND ANCHORAGE), OF THE STANDARD SPECIFICATIONS.

PROVIDE 1-1/8" AND 2-1/16" GALVANIZED STEEL SHIMS FOR 25% OF THE POSTS.

IF ONE ANCHOR BOLT FAILS DURING TEST, TWO OTHER ANCHOR BOLTS SHALL BE TESTED. TESTING EQUIPMENT CAN BE OBTAINED FROM BOLT COMPANIES.

## THIS SHEET IS FOR INFORMATION ONLY

FILE NAME =	USER NAME = midyja	DESIGNED -	REVISED - R. RITCHIE 05-02-00		TYPICAL DETAIL FOR CENTER LONGITUDINAL JOINT GUARDRAIL JOINT				IOINT	F.A	SECTION	COUNTY	TOTAL SHEET
W:\diststd\22x34\bm05.dgn		DRAWN - RFL	REVISED -	STATE OF ILLINOIS						VAR	2008-058 GRR	VARIOUS	21 11
	PLOT SCALE = 50.000 '/ IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION							BM-05	CONTRACT	RACT NO. 60F16
	PLOT DATE = 8/27/2008	DATE - 10-31-88	REVISED -		SCALE: NONE	SHEET NO. 1 OF 1 S	SHEETS	STA.	TO STA.	FED. ROAL	D DIST. NO. 1   ILLINOIS FED. AI		***************************************