


SUMMARY OF QUANTITIES

 A tyco INTERNATIONAL LTD. COMPANY	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	1463	1010.1B	COOK	171	4
STA.		TO STA.			
FED. ROAD DIST. NO.		ILLINOIS		FED. AID PROJECT	
CONTRACT NO. 62196					

PROJECT NAME: FAU 1463 (31st Street over MJ&CWI RR and Kilbourn Avenue)		UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES						
COUNTY: COOK				1000-2A	X571-2A	X271-2A	Y007	Y031-1F	Y030-1E	*
CODE NO.	PAY ITEM DESCRIPTION			Roadway	MJ&CWI RR	Kilbourn Ave.	Retaining Wall	Traffic Signal	Lighting	Lighting 100% Cicero
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	201	201						
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	134	134						
20101000	TEMPORARY FENCE	FOOT	5,150	5,150						
20101100	TREE TRUNK PROTECTION	EACH	27	27						
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	7	7						
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	11	11						
20200100	EARTH EXCAVATION	CU YD	82	82						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1,561	1,561						
20400800	FURNISHED EXCAVATION	CU YD	1,128	1,128						
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	158		84	74				
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	257	257						
20800150	TRENCH BACKFILL	CU YD	273	273						
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	300	300						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,245	4,245						
25000210	SEEDING, CLASS 2A	ACRE	0.50	0.50						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	320	320						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	320	320						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	320	320						
* 25000750	MOWING	ACRE	21.25	21.25						
25003210	INTERSEEDING, CLASS 2A	ACRE	3.00	3.00						
25003312	INTERSEEDING, CLASS 4A	ACRE	3.50	3.50						
25100115	MULCH, METHOD 2	ACRE	6.25	6.25						
25100630	EROSION CONTROL BLANKET	SQ YD	5,000	5,000						
25200110	SODDING, SALT TOLERANT	SQ YD	4,245	4,245						
25200200	SUPPLEMENTAL WATERING	UNIT	14	14						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100						
28000400	PERIMETER EROSION BARRIER	FOOT	2,950	2,950						
28000500	INLET AND PIPE PROTECTION	EACH	8	8						
28000510	INLET FILTERS	EACH	18	18						
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	3,987	3,987						
35300605	PORTLAND CEMENT CONCRETE BASE COURSE 11 1/4"	SQ YD	3,428	3,428						
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12	12						
40600300	AGGREGATE (PRIME COAT)	TON	17	17						
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	523	523						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	54	54						
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	59	59						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70	TON	700	700						
42000511	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	SQ YD	750	750						
42001300	PROTECTIVE COAT	SQ YD	3,650	3,650						
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	654	654						
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	135	135						
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	19,824	19,824						
42400610	TEMPORARY SIDEWALK	SQ FT	1,220	1,220						
44000100	PAVEMENT REMOVAL	SQ YD	4,556	4,556						
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	4,903	4,903						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2,631	2,631						
44000600	SIDEWALK REMOVAL	SQ FT	14,755	14,755						
44000700	APPROACH SLAB REMOVAL	SQ YD	575	575						
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	350	350						
44201349	CLASS C PATCHES, TYPE I, 10 INCH	SQ YD	100	100						
40600895	CONSTRUCTING TEST STRIP	EACH	1	1						

+ SPECIALITY ITEM
* NON PARTICIPATING ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
31st STREET

**SUMMARY OF QUANTITIES
I OF VI**

SCALE: VERT. N.T.S.
HORIZ. APRIL, 2008

DRAWN BY CJO
CHECKED BY MJE

Rev.