

**EXISTING DRAINAGE STRUCTURES AND STORM SEWER SCHEDULE**

STATION	OFFSET	DRAINAGE STRUCTURES TO BE CLEANED (EACH)	MANHOLES TO BE ADJUSTED (EACH)	REMOVING MANHOLES (EACH)	REMOVING CATCH BASINS (EACH)	REMOVING INLETS (EACH)	INLETS ADJ NEW T23 F&G (EACH)	CB ADJ NEW T23 F&G (EACH)	CB ADJ NEW F&PL CHICAGO (EACH)	SS TO BE CLEANED (FEET)	SS REMOVAL 10" (FEET)	SS REMOVAL 12" (FEET)	FRAMES AND LIDS TO BE ADJUSTED (EACH)
31st STREET													
205+07	100' RT.	1								140			
205+08	34' LT.	1	1							151			
205+10	72' RT.	1											
205+17	29' LT.				1								
205+17	30' RT.				1								
205+22	113' RT.	1								20			
205+22	134' RT.	1								21			
206+62	35' LT.	1								156			
206+63	85' RT.	1								157			
206+71	29' LT.	1						1		11			
206+72	30' RT.	1						1		58			
208+51	34' LT.	1								189			
208+62	23' LT.	1						1		16			
208+62	23' RT.	1					1			46			
208+56	65' RT.	1								617			
210+41	34' LT.	1								190			
210+51	23' LT.	1						1		15			
210+51	23' RT.	1					1			46			
212+31	34' LT.	1								190			
212+41	23' LT.	1						1		15			
212+41	23' RT.	1					1			45			
214+20	34' LT.	1								189			
214+31	23' LT.				1							15	
214+31	23' RT.					1						46	
220+01	23' LT.				1					52	6		
220+02	23' RT.				1						12		
220+11	33' RT.	1								119			
221+22	23' LT.				1					52	6		
221+22	23' RT.				1						12		
221+30	33' RT.	1								121			
222+42	23' LT.				1					52	6		
222+42	23' RT.				1								
222+51	33' RT.	1								85			
223+12	93' RT.	1								33			
224+92	24' LT.				1						58		
224+92	24' RT.				1						12		
225+02	34' RT.			1									
226+61	24' LT.				1						56		
226+61	24' RT.				1						10		
226+69	33' RT.			1									
227+10	8' RT.												1
228+31	24' LT.	1							1	58			
228+31	24' RT.	1							1	12			
228+40	33' RT.	1								118			
229+58	33' RT.	1								28			
229+73	24' LT.	1							1	17			
229+73	24' RT.	1							1	18			
229+76	80' LT.	1								56			
229+78	83' RT.	1								53			
CICERO AVENUE													
406+75	43' RT.					1				60			
TOTALS:		32	1	2	13	2	3	5	4	3206	178	61	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**31st STREET**

**SCHEDULE OF QUANTITIES**

**IV OF IV**

SCALE: VERT. N.T.S.  
HORIZ. N.T.S.

DATE: APRIL, 2008

DRAWN BY: CJO  
CHECKED BY: MJE