

F. A. U. NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2906	02-00077-00-WR	COOK	073	004
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT M-8003(596)	

CONTRACT #63061

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE						
					1000-2A	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031-1F	Y080
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	20	20						
	20101200	TREE ROOT PRUNING	EACH	9	9						
	20200100	EARTH EXCAVATION	CU YD	7854	7854						
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1107	1107						
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	407	407						
	20800150	TRENCH BACKFILL	CU YD	257	257						
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8450	8450						
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	100	100						
	25000210	SEEDING, CLASS 2A	ACRE	1.74	1.74						
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	158	158						
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	158	158						
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	158	158						
	25100630	EROSION CONTROL BLANKET	SQ YD	8450	8450						
	28000300	TEMPORARY DITCH CHECKS	EACH	1	1						
	28000400	PERIMETER EROSION BARRIER	FOOT	3800	3800						
	28000510	INLET FILTERS	EACH	34	34						
	35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	1000	1000						
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1390	1390						
	40600300	AGGREGATE (PRIME COAT)	TON	29	29						
	40600895	CONSTRUCTING TEST STRIP	EACH	2	2						
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7775	7775						
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	110	110						
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1805	1805						
	42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	410	410						
	44000100	PAVEMENT REMOVAL	SQ YD	11800	11800						
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2079	2079						
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1502	1502						
	44000600	SIDEWALK REMOVAL	SQ FT	105	105						
	48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	275	275						
	50104400	CONCRETE HEADWALL REMOVAL	EACH	2	2						
	54200427	PIPE CULVERTS, TYPE 1 RCCP 12"	FOOT	37	37						
	54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2						
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	651	651						
	55100400	STORM SEWER REMOVAL 10"	FOOT	18	18						
	55100500	STORM SEWER REMOVAL 12"	FOOT	21	21						
	55100700	STORM SEWER REMOVAL 15"	FOOT	165	165						
	55101100	STORM SEWER REMOVAL 21"	FOOT	113	113						
	55101600	STORM SEWER REMOVAL 36"	FOOT	30	30						
	55101800	STORM SEWER REMOVAL 42"	FOOT	20	20						
	55102000	STORM SEWER REMOVAL 54"	FOOT	40	40						
*	56106300	ADJUSTING WATER MAIN 6"	FOOT	25	25						
*	56106700	ADJUSTING WATER MAIN 16"	FOOT	250	250						
*	56400100	FIRE HYDRANTS TO BE MOVED	EACH	9	9						
*	56400600	FIRE HYDRANTS	EACH	2	2						
	60107600	PIPE UNDERDRAINS 4"	FOOT	515	515						
	60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	6	6						
	60205040	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2						
	60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	6	6						
	60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	6	6						
	60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
	60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
	60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1	1						
	60224460	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2	2						
	XX007122	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	3	3						

\* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

**ILLINOIS DEPARTMENT OF TRANSPORTATION**

**STATE STREET AND 168TH STREET  
INTERSECTION IMPROVEMENT  
SUMMARY OF QUANTITIES**

SCALE: VERT. NA  
 HORIZ. NA  
 DATE 7/22/08

DRAWN BY RG  
 CHECKED BY EA/PKB

ROBINSON ENGINEERING, LTD.  
 1700 SOUTH PARK AVENUE SOUTH HOLLAND, ILLINOIS 60473  
 (708) 331-6700 FAX (708) 331-3888  
 ILLINOIS DESIGN FIRM REGISTRATION NO. 154001158

07345-QUAN-01