

SUMMARY OF QUANTITIES				
CODE	PAY ITEM	UNIT	TOTAL QUANTITY	J000 80% Federal 20% Local
20101200	TREE ROOT PRUNING	EACH	20	20
20200410	EARTH EXCAVATION (SPECIAL)	CUYD	725	725
21101610	TOPSOIL FURNISH AND PLACE, 3"	SQYD	1,000	1,000
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18
25200110	SODDING, SALT TOLERANT	SQYD	1,000	1,000
25200200	SUPPLEMENTAL WATERING	UNIT	50	50
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100
42101300	PROTECTIVE COAT	SQYD	10,100	10,100
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQYD	600	600
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQYD	1,000	1,000
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQFT	31,000	31,000
42400800	DETECTABLE WARNINGS	SQFT	100	100
44000200	DRIVEWAY PAVEMENT REMOVAL	SQYD	1,600	1,600
44000600	SIDEWALK REMOVAL	SQFT	600	600
44001700	COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2,500	2,500
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQYD	3,700	3,700
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQYD	100	100
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQYD	100	100
44213200	SAW CUTS	FOOT	23,600	23,600
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	1	1
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	25	25
67100100	MOBILIZATION	L SUM	1	1
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQFT	175	175
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	19,000	19,000
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	1,100	1,100
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	500	500
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	500	500
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	100	100
X0322256	TEMPORARY INFORMATION SIGNING	SQFT	50	50
Z0017202	DOWEL BARS 1 1/2"	EACH	5,200	5,200
Z0075310	TIE BARS 3/4"	EACH	35	35

* DENOTE SPECIALTY ITEMS

Drawing file: W:\Projects\80008062 - 25th Ave Improvement\Summary.dwg Jul 23, 2008 - 4:23pm



♦ Civil Engineers
 ♦ Municipal Consultants
 ♦ Established 1911
 9933 Roosevelt Road
 Westchester, Illinois 60154-2780
 Phone: 708/865-0300
 Fax: 708/865-1212

REVISION:	

SCHILLER PARK
25th AVENUE IMPROVEMENT
SUMMARY OF QUANTITIES

NONE
 DRAWN BY: LEV, DMM, MK
 CHECKED BY: BP
 DATE: 7/23/2008

SCALE: NOT TO SCALE