

FAU R/E	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
3803	03-00049-00-FP	COOK	045	004
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT M8003 (559)	

CONTRACT #63078

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING	LOCAL AGENCY
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE							
					1000-2A	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031	Y080	Y060
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	42	42							
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	225	225							
	20200100	EARTH EXCAVATION	CU YD	2878	2878							
	20200200	ROCK EXCAVATION	CU YD	100	100							
	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	100	100							
	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	100	100							
	20800150	TRENCH BACKFILL	CU YD	6600	4660						2000	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4995	4995							
	21300010	EXPLORATION TRENCH, SPECIAL	FOOT	200	200							
*	25000210	SEEDING, CLASS 2A	ACRE	0.491	0.491							
*	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	77	77							
*	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	77	77							
*	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	77	77							
	25100630	EROSION CONTROL BLANKET	SQ YD	2375	2375							
*	25200110	SODDING, SALT TOLERANT	SQ YD	2620	2620							
	28000400	PERIMETER EROSION BARRIER	FOOT	4170	4170							
	28000500	INLET AND PIPE PROTECTION	EACH	1	1							
	28000510	INLET FILTERS	EACH	38	38							
	28100107	STONE RIPRAP, CLASS A4	SQ YD	12	12							
	28200200	FILTER FABRIC	SQ YD	12	12							
	35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1818	1818							
	35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	357	357							
	40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	120	120							
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3905	3905							
	40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	2	2							
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	83	83							
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1380	1380							
	40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1709	1709							
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	41	41							
	40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1256	1256							
	42001300	PROTECTIVE COAT	SQ YD	3319	3319							
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	17865	17865							
	42400800	DETECTABLE WARNINGS	SQ FT	66	66							
	44000100	PAVEMENT REMOVAL	SQ YD	948	948							
	44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1024	1024							
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	306	306							
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	936	936							
	44000600	SIDEWALK REMOVAL	SQ FT	17310	17310							
	44004250	PAVED SHOULDER REMOVAL	SQ YD	1711	1711							
	44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	95	95							
	44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	136	136							
	44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	527	527							
	44300300	AREA REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A	SQ YD	9160	9160							
	54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1							
	54247170	GRATING FOR CONCRETE FLARED END SECTION 36"	EACH	1	1							
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	259	259							
	550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	67	67							
	550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	993	993							
	550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	204	204							
	550A0730	STORM SEWERS, CLASS A, TYPE 3 30"	FOOT	640	640							
	550A0750	STORM SEWERS, CLASS A, TYPE 3 36"	FOOT	586	586							

\* - INDICATES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**MAIN STREET IMPROVEMENTS**  
**NORTH MAIN STREET TO CAMPBELL STREET**  
**SUMMARY OF QUANTITIES**

SCALE: VERT. NA  
 HORIZ. NA  
 DATE: 7-24-08  
 DRAWN BY: LTL  
 CHECKED BY: WPD