

X028-2A

CODE NUMBER	PAY ITEM	UNIT	80% FED. 20% STATE TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	26
20200100	EARTH EXCAVATION	CU YD	1566
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	203
* 25000210	SEEDING, CLASS 2A	ACRE	0.72
* 25000310	SEEDING, CLASS 4	ACRE	0.22
* 25000750	MOWING	ACRE	0.94
* 25100115	MULCH, METHOD 2	ACRE	0.94
28000300	TEMPORARY DITCH CHECKS	EACH	22
28000400	PERIMETER EROSION BARRIER	FOOT	300
28000500	INLET ^{AND} PIPE PROTECTION	EACH	3
28100107	STONE RIPRAP, CLASS A4	SQ YD	154
28200200	FILTER FABRIC	SQ YD	154
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	495
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	17.2
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	300.6
44213100	PAVEMENT FABRIC	SQ YD	246.0
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	246.0
44213200	SAW CUTS	FOOT	163.0
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	57.0
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	170.4
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.0
50800105	REINFORCEMENT BARS	POUND	46560.0
51500100	NAME PLATES	EACH	1
54003000	CONCRETE BOX CULVERT	CU YD	239.1
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	36

● NP 100% STATE * SPECIALTY ITEMS

FILE NAME = c:\projects\p202604\d02604cvr.dgn	USER NAME = grantpm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.S RTE. 2076	SECTION 101T-1	COUNTY CARROLL	TOTAL SHEETS 31	SHEET NO. 3
	PLOT SCALE = 75.0000' / IN.	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		
	PLOT DATE = Mon Aug 04 08:36:59 2008	CHECKED -	REVISED -								CONTRACT NO. 64979		
		DATE -	REVISED -										