

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNITS	LOCATION
26.0	LT & RT Sta 246+05.0
26.0	TOTAL

20200100 EARTH EXCAVATION

CU. YD.	LOCATION
1466.0	LT & RT Sta 242+00.0 TO 250+00.0
100.0	LT & RT Sta 246+05.0
1566.0	TOTAL

25000210 SEEDING, CLASS 2A

ACRE	LOCATION
0.37	LT Sta. 242+00.0 TO 250+00.0
0.35	RT Sta. 242+00.0 TO 250+00.0
0.72	TOTAL

25000310 SEEDING, CLASS 4

ACRE	LOCATION
0.12	LT Sta. 242+00.0 TO 250+00.0
0.10	RT Sta. 242+00.0 TO 250+00.0
0.22	TOTAL

25100115 MULCH, METHOD 2

ACRE	LOCATION
0.49	LT Sta. 242+00.0 TO 250+00.0
0.45	RT Sta. 242+00.0 TO 250+00.0
0.94	TOTAL

28000300 TEMPORARY DITCH CHECKS

EACH	LOCATION
5	RT Sta. 242+00.0 TO 246+05.0
3	LT Sta. 242+00.0 TO 246+05.0
7	RT Sta. 250+00.0 TO 246+05.0
7	LT Sta. 250+00.0 TO 246+05.0
22	TOTAL

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION
300	LT Sta. 242+00.0 TO 250+00.0
300	TOTAL

28000500 INLET PIPE PROTECTION

EACH	LOCATION
1	LT Sta. 243+00.0
1	RT Sta. 244+20.0
1	LT Sta. 245+05.0
3	TOTAL

REMARKS
ENTIRE PROJECT

28100107 STONE RIPRAP, CLASS A4

SQ. YD.	LOCATION
77.0	RT Sta. 246+05.0
77.0	LT Sta. 246+05.0
154.0	TOTAL

DIMENSION
693 SQ FT
693 SQ FT

REMARKS
D/S End of Culvert
U/S End of Culvert

REMARKS
ENTIRE PROJECT
ESTIMATED U/S & D/S CHANNEL EXCAVATION

28200200 FILTER FABRIC

SQ. YD.	LOCATION
77.0	RT Sta. 246+05.0
77.0	LT Sta. 246+05.0
154.0	TOTAL

DIMENSION
693 SQ FT
693 SQ FT

REMARKS
D/S End of Culvert
U/S End of Culvert

REMARKS

35102000 AGGREGATE BASE COURSE, TYPE B 8"

SQ. YD.	LOCATION
100.0	LT Sta. 243+25.0
158.0	RT Sta. 244+50.0
237.0	LT Sta. 245+42.0
495.0	TOTAL

THICKNESS (in)
8.0
8.0
8.0

REMARKS
Field Entrance
Field Entrance
Field Entrance

REMARKS

40600625 LEVELING BINDER (MACHINE METHOD) N50

TON	LOCATION
8.60	LT Sta. 245+62.0 TO 246+47.0
8.60	RT Sta. 245+62.0 TO 246+47.0
17.20	TOTAL

THICKNESS (in)
1.0
1.0

REMARKS
85 x 13 - One Lane - CLASS B PATCH
85 x 13 - One Lane - CLASS B PATCH

REMARKS

40603310 HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50

TON	LOCATION
10.30	Sta. 245+62.0 TO 246+47.0
10.30	Sta. 245+62.0 TO 246+47.0
147.00	IDEAL ROAD
133.00	THOMSON ROAD
300.60	TOTAL

THICKNESS (in)
1.5
1.5
1.5
1.5

REMARKS
85 x 13 - One Lane - CLASS B PATCH
85 x 13 - One Lane - CLASS B PATCH
Good neighbor Policy (as needed)
Good neighbor Policy (as needed)

REMARKS

44213100 PAVEMENT FABRIC

SQ. YD.	LOCATION
123.0	LT Sta. 245+62.0 TO 246+47.0
123.0	RT Sta. 245+62.0 TO 246+47.0
246.0	TOTAL

REMARKS
85 x 13 - One Lane
85 x 13 - One Lane

REMARKS
ENTIRE PROJECT

44201037 CLASS B PATCHES, TYPE IV, 15 INCH

SQ. YD.	LOCATION
123.0	LT Sta. 245+62.0 TO 246+47.0
123.0	RT Sta. 245+62.0 TO 246+47.0
246.0	TOTAL

REMARKS
85 x 13 - One Lane
85 x 13 - One Lane