

44213200 SAW CUTS

FOOT	LOCATION		
39.0	LT Sta.	245+62.0 TO	246+47.0
39.0	RT Sta.	245+62.0 TO	246+47.0
<u>85.0</u>	RT & LT Sta	245+62.0 TO	246+47.0
163.0	TOTAL		

REMARKS
3 CUTS @ 13'
3 CUTS @ 13'
CENTERLINE CUT

48101500 AGGREGATE SHOULDERS, TYPE B 6"

SQ YD	LOCATION		
28.3	RT Sta.	245+62.0 TO	246+47.0
<u>28.3</u>	LT Sta.	245+62.0 TO	246+47.0
56.6	TOTAL		

REMARKS
LIMITS OF PATCH AREA
LIMITS OF PATCH AREA

48102100 AGGREGATE WEDGE SHOULDER, TYPE B

TON	LOCATION		
20.6	RT Sta.	242+00.0 TO	245+62.0
20.6	RT Sta.	246+47.0 TO	250+00.0
20.6	LT Sta.	242+00.0 TO	245+62.0
20.6	LT Sta.	246+47.0 TO	250+00.0
42.0		IDEAL ROAD	
<u>46.0</u>		THOMSON ROAD	
170.4	TOTAL		

REMARKS
3" WEDGE
3" WEDGE
3" WEDGE
3" WEDGE
1.5" WEDGE Good neighbor Policy (as needed)
1.5" WEDGE Good neighbor Policy (as needed)

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

EACH	LOCATION	
<u>1</u>	RT Sta.	244+50.0
1	TOTAL	

REMARKS
EXISTING 3' X 2' BOX CULVERT
UNDER FIELD ENTRANCE

50100400 REMOVAL OF EXISTING STRUCTURES NO. 2

EACH	LOCATION	
<u>1</u>	Sta.	246+05.0
1	TOTAL	

REMARKS
EXISTING 2-CELL 11' X 6' BOX CULVERT

50800105 REINFORCEMENT BARS

POUNDS	LOCATION	
<u>44640.0</u>	Sta.	246+05.0
46560.0	TOTAL	

REMARKS
2-CELL 14' X 4' CAST-IN- PLACE BOX CULVERT

51500100 NAME PLATES

EACH	LOCATION	
<u>1.0</u>	Sta.	246+05.0
1.0	TOTAL	

REMARKS
2-CELL 14' X 4' CAST-IN- PLACE BOX CULVERT

54003000 CONCRETE BOX CULVERT

CU. YD.	LOCATION	
<u>239.1</u>	Sta.	246+05.0
239.1	TOTAL	

REMARKS
2-CELL 14' X 4' CAST-IN- PLACE BOX CULVERT

542D0223 PIPE CULVERTS CLASS D, TYPE 1, 18"

FOOT	LOCATION	
<u>36.0</u>	LT. Sta.	243+25.0
36.0	TOTAL	

REMARKS
FIELD ENTRANCE

542D0229 PIPE CULVERTS CLASS D, TYPE 1, 24"

FOOT	LOCATION	
<u>60.0</u>	LT. Sta.	245+42.0
60.0	TOTAL	

REMARKS
FIELD ENTRANCE

542D0241 PIPE CULVERTS CLASS D, TYPE 1, 36"

FOOT	LOCATION	
<u>46.0</u>	RT. Sta.	244+50.0
46.0	TOTAL	

REMARKS
FIELD ENTRANCE

54213453 END SECTIONS 18"

EACH	LOCATION	
<u>2.0</u>	LT. Sta.	243+25.0
2.0	TOTAL	

REMARKS
FIELD ENTRANCE

54213459 END SECTIONS 24"

EACH	LOCATION	
<u>2.0</u>	LT. Sta.	245+42.0
2.0	TOTAL	

REMARKS
FIELD ENTRANCE

54213471 END SECTIONS 36"

EACH	LOCATION	
<u>2.0</u>	RT. Sta.	244+50.0
2.0	TOTAL	

REMARKS
FIELD ENTRANCE

61100500 EXPLORATION TRENCH 52" DEPTH

FOOT	LOCATION	
<u>100.0</u>	LT & RT. Sta	246+05.0
100.0	TOTAL	

REMARKS
LOCATIONS TO BE DETERMINED IN FIELD

61133100 FIELD TILE JUNCTION VAULTS, 2' DIA

EACH	LOCATION	
<u>2.0</u>	LT & RT. Sta	246+05.0
2.0	TOTAL	

REMARKS
LOCATIONS TO BE DETERMINED IN FIELD