

SCHEDULE OF QUANTITIES

78200410 GUARDRAIL MARKERS, TYPE A

EACH	LOCATION	REMARKS
5	LT. STA. 341+ 8 TO 344+	14 @ 80' spacing
19	LT. STA. 345+ 16 TO 358+	98 @ 80' spacing
4	RT. STA. 342+ 31 TO 344+	37 @ 80' spacing
19	RT. STA. 345+ 40 TO 359+	21 @ 80' spacing
47	TOTAL	

78200520 BARRIER WALL MARKERS, TYPE B

EACH	LOCATION	REMARKS
6	344+ 76	3 on each parapet wall
6	TOTAL	

78201000 TERMINAL MARKERS (DIRECT APPLIED)

EACH	LOCATION	REMARKS
1	LT. STA. 340+ 58	
1	RT. STA. 341+ 81	
1	LT. STA. 359+ 48	
1	RT. STA. 359+ 71	
4	TOTAL	

78300100 PAVEMENT MARKING REMOVAL

SQ. FT.	LOCATION	REMARKS
STAGE 2		
26.3	CL 336+ 34 TO 339+	50 Skips - Stage 2
394.8	RT. STA. 338+ 7 TO 349+	92 Edge Line - Stage 2
17.4	CL 349+ 50 TO 351+	59 Skips - Stage 2
STAGE 3		
369.3	338+ 55 TO 349+	63 Edge Line - Stage 3
807.9	TOTAL	

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION	REMARKS
13	CL 339+ 0 TO 348+	55
13	TOTAL	

Z0005300 BOX CULVERTS TO BE CLEANED

EACH	LOCATION	REMARKS
1	LYRT 338+ 45	Existing 4' x 2' box culvert
1	TOTAL	

Z0010555 DITCH CLEANING

FOOT	LOCATION	REMARKS
1320.0	LT. STA. 325+ 80 TO 339+	0
1320.0	RT. STA. 325+ 80 TO 339+	0
2640.0	TOTAL	

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARKS
1	LT. STA. 338+ 3	Stage 2
1	LT. STA. 350+ 2	Stage 2
2	TOTAL	

Z0030335 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3

EACH	LOCATION	REMARKS
1	RT. STA. 338+ 40	Stage 3
1	RT. STA. 349+ 65	Stage 3
2	TOTAL	