

EARTHWORK SCHEDULE

	LOCATION	20200100	EARTHWORK			20400800	25000210	25100105	28000250	21101625
		EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	FURNISHED EXCAVATION	SEEDING CLASS 2A	MULCH, METHOD 1	TEMPORARY EROSION CONTROL SEEDING	TOPSOIL FURNISH & PLACE, 6"
		(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(ACRE)	(ACRE)	(POUND)	(SQ YD)
Mainline (IL 84)										
	339 + 00 TO 343 + 00	174.7	131.0	711.8	-580.8	580.8	0.39	0.23	157.7	1975.2
	343 + 00 TO 349 + 00	98.3	73.7	1004.8	-931.1	931.1	0.54		215.9	2612.9
	349 + 00 TO 355 + 00	332.0	249.0	661.5	-412.5	412.5	0.56		222.7	2694.9
	355 + 00 TO 360 + 70	290.7	218.0	369.5	-151.5	151.5	0.41	0.07	165.2	1999.3
W. Ebson Rd.	1202 + 46.02 TO 1203 + 00	53.9	40.4	3.8	36.6	36.6	0.02	0.02	7.1	86.4
E. Ebson Rd.	1000 + 50 TO 1001 + 95	85.8	64.4	246.6	-182.3	182.3	0.09	0.09	36.6	442.7
	TOTALS	1035.4	776.6	2998.0	-2221.5	2221.5	2.01	0.40	805.4	9811.4