

CODE NO	ITEM	UNIT	TOTAL QTY 90% FED. 10% ST.	CONSTRUCTION TYPE CODE															
				RDWY 1000-2A	006- 0001 X071-2A	006- 0002 X071-2A	006- 0003 X071-2A	006- 0004 X071-2A	006- 0005 X071-2A	006- 0006 X071-2A	006- 0007 X071-2A	006- 0008 X071-2A	006- 0009 X071-2A	006- 0010 X071-2A	006- 0011 X071-2A	006- 0012 X071-2A	006- 0121 X071-2A		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4516	4516															
48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SO YD	443	443															
48300400	PORTLAND CEMENT CONCRETE SHOULDERS 9"	SO YD	5,650	5,650															
50102400	CONCRETE REMOVAL	CU YD	79.5								19.8	19.7	20	20					
50104650	SLOPE WALL REMOVAL	SO YD	491			71	71	72	72	90	90			9	16				
50105210	REMOVE EXISTING CULVERTS	FOOT	48	48															
50157300	PROTECTIVE SHIELD	SQ YD	300															300	
50200100	STRUCTURE EXCAVATION	CU YD	449								109	109	115	116					
50300100	FLOOR DRAINS	EACH	50								18	18	7	7					
50300225	CONCRETE STRUCTURES	CU YD	130.4								33.2	33.2	32	32					
50300255	CONCRETE SUPERSTRUCTURE	CU YD	716.9								203.6	203.6	154.8	154.9					
50300260	BRIDGE DECK GROOVING	SQ YD	2077								582	582	456.5	456.5					
50300300	PROTECTIVE COAT	SQ YD	2685								745	745	597.5	597.5					
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	8760								2285	2285	2095	2095					
50500505	STUD SHEAR CONNECTORS	EACH	13556								3600	3600	3178	3178					
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	64								18	18	14	14					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	157680								43260	43260	35580	35580					
50800515	BAR SPLICERS	EACH	1636								442	442	376	376					
51100100	SLOPE WALL 4 INCH	SO YD	25										9	16					
51500100	NAME PLATES	EACH	4								1	1	1	1					
52000110	PREFORMED JOINT STRIP SEAL	FOOT	355								92.5	92.5	85	85					
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	46								9	9	14	14					
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18								9	9							
52100520	ANCHOR BOLTS, 1"	EACH	128								36	36	28	28					
542A0229	PIPE CULVERTS, CLASS A, TYPE I 24"	FOOT	12	12															
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1															1	
542A0235	PIPE CULVERTS, CLASS A, TYPE I 30"	FOOT	6	6															
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	3															3	
542A0241	PIPE CULVERTS, CLASS A, TYPE I 36"	FOOT	30	30															
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1															1	
59000200	EPOXY CRACK INJECTION	FOOT	283								86	64	68	65					
54248515	CONCRETE COLLAR	EACH	8															8	
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1	1															
60260100	INLETS TO BE ADJUSTED	EACH	2	2															
60500060	REMOVING INLETS	EACH	1	1															
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1095	1095															
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	8	8															
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	16	16															
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1															
63200310	GUARDRAIL REMOVAL	FOOT	1857	1857															
* 63500105	DELINEATORS	EACH	273	273															
63500120	DELINEATOR REMOVAL	EACH	273	273															
64200105	SHOULDER RUMBLE STRIP	FOOT	193822	193822															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12															

* SPECIALTY ITEMS

FILE NAME =	USER NAME = braboypc	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
es:\pw_work\pwsdot\braboypc\dms32763\dets1.s.dgn	DRAWN - ---	REVISED - ---	REVISED - ---									80	06-1,2,RS-3, I	BUREAU	116	4			
PLOT SCALE = 20,0000' / IN.	CHECKED - ---	REVISED - ---	REVISED - ---									SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____				FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT			
PLOT DATE = Sep 04, 2008 - 04:06:41 PM	DATE - -----	REVISED - ---	REVISED - ---									CONTRACT NO. 66623							