

SUMMARY OF QUANTITIES

CONTRACT NO. 66667				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	129 BR	KENDALL	61	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL 80% FED 20% STATE	ROADWAY 1000	BRIDGE	BRIDGE
					EXIST. SN 047-0016 PROP. SN 047-2019 X078-2A	EXIST. SN 047-0046 PROP. SN 047-2020 X988-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	203	203		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	211	211		
20101000	TEMPORARY FENCE	FOOT	400	400		
20200100	EARTH EXCAVATION	CU YD	575	575		
20400800	FURNISHED EXCAVATION	CU YD	15	15		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1811	1811		
21400100	GRADING AND SHAPING DITCHES	FOOT	637	637		
25000300	SEEDING, CLASS 3	ACRE	0.5	0.5		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	34	34		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	34	34		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	34	34		
25100115	MULCH, METHOD 2	ACRE	0.5	0.5		
28000300	TEMPORARY DITCH CHECKS	EACH	5	5		
28000400	PERIMETER EROSION BARRIER	FOOT	400	400		
28100109	STONE RIPRAP, CLASS A5	SQ YD	1081	1081		
28200200	FILTER FABRIC	SQ YD	1081	1081		
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	249	249		
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	249	249		
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	1083	1083		
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	40	40		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	244	244		
40600300	AGGREGATE (PRIME COAT)	TON	6	6		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	62.5	62.5		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	320	320		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	232	232		

PAY CODE NUMBER	PAY ITEM	UNIT	TOTAL 80% FED 20% STATE	ROADWAY 1000	BRIDGE	BRIDGE
					EXIST. SN 047-0016 PROP. SN 047-2019 X078-2A	EXIST. SN 047-0046 PROP. SN 047-2020 X988-2A
44000100	PAVEMENT REMOVAL	SQ YD	297	297		
48203046	HOT-MIX ASPHALT SHOULDERS, 12 1/4"	SQ YD	146	146		
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		1	1
50105220	PIPE CULVERT REMOVAL	FOOT	70	70		
50300225	CONCRETE STRUCTURES	CU YD	26.2		26.2	
50500505	STUD SHEAR CONNECTORS	EACH	273		273	
*50700209	UNTREATED TIMBER LAGGING	SQ FT	470		470	
51202210	FURNISHING SOLDIER PILES (HP SECTION)	FOOT	465		465	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	13400		13400	
51500100	NAME PLATES	EACH	2		1	1
54001000	BOX CULVERT END SECTIONS	EACH	4			4
54000008	PRECAST CONCRETE BOX CULVERT 10' X 8'	FOOT	90		90	
54003000	CONCRETE BOX CULVERTS	CU YD	64.8		64.8	
54021210	PRECAST CONCRETE BOX CULVERT 12' X 10' (M273)	FOOT	80			80
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	52		52	
*63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	839	839		
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	124		68	56
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4		
63200310	GUARDRAIL REMOVAL	FOOT	692	692		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	10	10		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION STANDARD 701201	L SUM	1	1		

* SPECIALTY ITEM

△ REVISED 10/30/08

PLOT DATE = Aug 06, 2008 - 02:31:08 PM
 PLOT SCALE = 5/8" = 1' / IN.
 USER NAME = wenzelko