

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
607	129 BR	KENDALL	61	8
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

67000400 ENGINEER'S FIELD OFFICE, TYPE A CAL MO

67100100 MOBILIZATION LUMP SUM
1

70100405 TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 LUMP SUM
1

70100450 TRAFFIC CONTROL AND PROTECTION STANDARD 701201 LUMP SUM
1

70100460 TRAFFIC CONTROL AND PROTECTION STANDARD 701306 LUMP SUM
1

70100500 TRAFFIC CONTROL AND PROTECTION, STANDARD 701326 LUMP SUM
1

70103815 TRAFFIC CONTROL SURVEILLANCE CAL DAY
45

70106500 TEMPORARY BRIDGE TRAFFIC SIGNALS EACH
1

70106700 TEMPORARY RUMBLE STRIP EACH
6

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

LOCATION	STAGE	SIDE	FT
STA. 104+80.50 TO STA. 111+33.50	STAGE 1	LEFT	655
STA. 103+76.00 TO STA. 112+38.00	STAGE 1	RIGHT	862
STA. 103+76.00 TO STA. 112+38.00	STAGE 2	LEFT	862
STA. 104+80.50 TO STA. 111+33.50	STAGE 2	RIGHT	655
TOTAL			3034

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

LOCATION	STAGE	FT
STA. 103+76.00	STAGE 1	12
STA. 112+38.00	STAGE 1	12
TOTAL		24

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	STAGE	SIDE	FT
STA. 104+80.50 TO STA. 111+33.50	STAGE 1	LEFT	218
STA. 103+76.00 TO STA. 112+38.00	STAGE 1	RIGHT	287
STA. 103+76.00 TO STA. 112+38.00	STAGE 2	LEFT	287
STA. 104+80.50 TO STA. 111+33.50	STAGE 2	RIGHT	218
STA. 103+76.00	STAGE 2		24
STA. 112+38.00	STAGE 2		24
TOTAL			1058

70400100 TEMPORARY CONCRETE BARRIER

LOCATION	FT
STA. 105+81.00 TO STA. 110+33.00	474
TOTAL	474

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	FT
STA. 105+81.00 TO STA. 110+33.00	474
TOTAL	474

78001110 PAINT PAVEMENT MARKING-LINE 4"

LOCATION	SIDE	FT
STA. 104+80.50 TO STA. 111+33.50	LEFT	655
STA. 104+80.50 TO STA. 111+33.50	RIGHT	655
TOTAL		1310

78001130 PAINT PAVEMENT MARKING-LINE 6"

LOCATION	SIDE	FT
STA. 103+76.00 TO STA. 112+38.00	CENTER	216
TOTAL		216

78100100 RAISED REFLECTIVE PAVEMENT MARKERS EACH
9

78200410 GUARDRAIL MARKERS, TYPE A EACH
17

78201000 TERMINAL MARKER - DIRECT APPLIED EACH
3

78300100 PAVEMENT MARKING REMOVAL

LOCATION	SIDE	SO FT
STA. 103+76.00 TO STA. 105+20.00	CENTER	12
STA. 110+94.00 TO STA. 112+38.00	CENTER	12
STA. 104+80.50 TO STA. 111+33.50	LEFT	218
STA. 104+80.50 TO STA. 111+33.50	RIGHT	218
TOTAL		460

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH
9

XX000061 STUMP REMOVAL

LOCATION	NO.
SW QUAD.	1
SE QUAD.	1
TOTAL	2

X7200201 WIDTH RESTRICTION SIGNING LUMP SUM
1

LOCATIONS	NO.
ON US 52 JUST EAST OF IL 47	1
BEFORE ALL TRAFFIC CONTROL SIGNING FOR EB TRAFFIC FOR TC&P STD 701326	1
BEFORE ALL TRAFFIC CONTROL SIGNING FOR WB TRAFFIC FOR TC&P STD 701326	1
ON US 52 WEST OF IL 59 IN SHOREWOOD	1
TOTAL NEEDED	4

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULE OF QUANTITIES</p> <p>SCALE: VERT. NOT TO SCALE HORIZ. NOT TO SCALE DATE 10/17/2007</p> <p>DRAWN BY C. SUNTKEN CHECKED BY W. ZELINSKAS</p>