

SUMMARY OF QUANTITIES								80%/20% FED./STATE			
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	TOTAL QUANT	X088-2A	X088-2A	X088-2A	X020-2A				
				027-2015	027-2016	027-2014	027-0095				
				ACBRF QUANT	ACBRF QUANT	ACF QUANT	ACF QUANT				
20200100	EARTH EXCAVATION	CU YD	815	320	170	50	275				
20300100	CHANNEL EXCAVATION	CU YD	390				390				
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1386	590	284	512					
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	378.8	44	37	227	70.8				
21400100	GRADING AND SHAPING DITCHES	FOOT	3266	1062	1100	1104					
25000300	SEEDING, CLASS 3	ACRE	1.68	.37	.44	.37	0.5				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	150	33	39	33	45				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	150	33	39	33	45				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	150	33	39	33	45				
25100630	EROSION CONTROL BLANKET	SQ YD	10368	2582	2530	2836	2420				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	268	37	44	37	150				
28000300	TEMPORARY DITCH CHECKS	EACH	38	10	9	10	9				
28000400	PERIMETER EROSION BARRIER	FOOT	891	306	485	100					
28000500	INLET AND PIPE PROTECTION	EACH	6	2	1	3					
28100107	STONE RIPRAP, CLASS A4	SQ YD	1908	437	389	555	527				
28200200	FILTER FABRIC	SQ YD	1908	437	389	555	527				
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	695	217	276	202					
35501327	HOT-MIX ASPHALT BASE COURSE, 10 3/4"	SQ YD	599	187	238	174					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	27				27				
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	743	161	160	134	288				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	1	1	1					
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	207	83	26	42	56				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1280	320	320	320	320				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	624	169	168	141	146				
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	194				194				
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	44				44				
44000100	PAVEMENT REMOVAL	SQ YD	1112	231	355	225	301				
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	3771	1162	1329	1280					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	71	10	23	20	18				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2975	797	844	788	546				
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1							
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1			1					
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		1						

SUMMARY OF QUANTITIES (CONTINUED)											80%/20% FED./STATE			
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	TOTAL QUANT	X088-2A	X088-2A	X088-2A	X020-2A							
				027-2015	027-2016	027-2014	027-0095							
				ACBRF QUANT	ACBRF QUANT	ACF QUANT	ACF QUANT							
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1							1				
50105200	REMOVE EXISTING CULVERTS	EACH	4	2	1		1							
50200100	STRUCTURE EXCAVATION	CU YD	2850	867	515	1348	120							
50300100	FLOOR DRAINS	EACH	8				8							
50300225	CONCRETE STRUCTURES	CU YD	73.8				73.8							
50300255	CONCRETE SUPERSTRUCTURE	CU YD	162.8				162.8							
50300260	BRIDGE DECK GROOVING	SQ YD	252				252							
50300300	PROTECTIVE COAT	SQ YD	540				540							
50800105	REINFORCEMENT BARS	POUND	27890	5050	16370	6470								
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	35130	790	350	1080	32910							
51201400	FURNISHING STEEL PILES HP10X42	FOOT	766				766							
51202305	DRIVING PILES	FOOT	766				766							
51203400	TEST PILE STEEL HP10X42	EACH	2				2							
51500100	NAME PLATES	EACH	4	1	1	1	1							
54003000	CONCRETE BOX CULVERTS	CU YD	187	51	70	66								
54011208	PRECAST CONCRETE BOX CULVERT 12' X 8'	FOOT	98	98										
54021006	PRECAST CONCRETE BOX CULVERT 10' X 6' (M273)	FOOT	64		64									
54021210	PRECAST CONCRETE BOX CULVERT 12' X 10' (M273)	FOOT	84			84								
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	42				42							
54200223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	77	77										
54200223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	30		30									
54213447	END SECTIONS 12"	EACH	4				4							
54213450	END SECTIONS 15"	EACH	2				2							
54213453	END SECTIONS 18"	EACH	6	4	2									
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	44				44							
60100945	PIPE DRAINS 12"	FOOT	36				36							
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	110				110							
60900140	TYPE B INLET BOX, STANDARD 609006	EACH	4				4							
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	1875	437.5	612.5	300	525							
63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	225	100	75	50								
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4				4							
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	10	2	4		4							
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	6	2		4								

\* SPECIALITY ITEM

FILE NAME =	USER NAME = lindemannms	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE. 798	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwwork\PIWDOT\LINDEMANMS\dms30072	d366698-ah-cover.dgn	DRAWN -	REVISED -						FORD	92	3	
	PLOT SCALE = 50,0000' / IN.	CHECKED -	REVISED -					CONTRACT NO. 66698				
	PLOT DATE = Aug 28, 2008 - 09:07:13 AM	DATE -	REVISED -					SCALE:	SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.

\* (107)BR & BR-1, (108)BR & BR-1