

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	.	**	219	3
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT				
* 106-14 & 50-81RS-1(14B,B-1,VB,VB-1,VB-2,VB-3)BR				
** BUREAU & LASALLE				

CODE NO	ITEM	UNIT	TOTAL QTY	90/10 FED/STATE		90/10 FED/STATE	90/10 FED/STATE	90/10 FED/STATE		90/10 FED/STATE	
				SUMMARY OF QUANTITIES		ACBRT	ACIM	CONSTRUCTION TYPE CODE		ACIM	
				ROADWAY		EXIST. SN	EXIST. SN	EXIST. SN	EXIST. SN		
		BUREAU COUNTY	LASALLE COUNTY	006-0032(EB)	006-0033(WB)	006-0034 (TBR)	006-0035 (TBR)	006-0036(EB)	006-0037(WB)		
		I000	I000	PROP. SN	PROP. SN			PROP. SN	PROP. SN		
				006-0165	006-0166			006-0167	006-0168		
				X071-2A	X071-2A			X171-2A	X171-2A		
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	714	714							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	241	241							
20200100	EARTH EXCAVATION	CU YD	2568	2568							
20400800	FURNISHED EXCAVATION	CU YD	55407	55407							
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	560		161	161		119	119		
* 25000300	SEEDING, CLASS 3	ACRE	7.3	7.3							
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	657	657							
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	657	657							
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	657	657							
* 25100115	MULCH, METHOD 2	ACRE	2.4	2.4							
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	23232	23232							
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2190	2190							
* 28000300	TEMPORARY DITCH CHECKS	EACH	40	40							
* 28000400	PERIMETER EROSION BARRIER	FOOT	4169	4169							
28000500	INLET AND PIPE PROTECTION	EACH	5	5							
28100107	STONE RIPRAP, CLASS A4	SQ YD	3096		1548	1548					
28200200	FILTER FABRIC	SQ YD	3096		1548	1548					
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	938	938							
35501343	HOT-MIX ASPHALT BASE COURSE, 15"	SQ YD	938	938							
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	7271	7271							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	13343	9187	4156						
40600300	AGGREGATE (PRIME COAT)	TON	336	232	104						
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	50	34	16						
40600555	LEVELING BINDER (HAND METHOD), N105	TON	83	57	26						
40600895	CONSTRUCTING TEST STRIP	EACH	3		3						
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3200	2080	1120						
40600990	TEMPORARY RAMP	SQ YD	426	293	133						
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	36757	30211	6546						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	10675	7239	3436						
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1320.8	966.8	354						
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	17068	11908	5160						
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	1064	1064							
42001200	PAVEMENT FABRIC	SQ YD	902	870	32						
44000100	PAVEMENT REMOVAL	SQ YD	1064	1064							
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	166911	114959	51952						
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	11793	8633	3160						
44000182	HOT-MIX ASPHALT SURFACE REMOVAL, 8"	SQ YD	7271	7271							
44213200	SAW CUTS	FOOT	16100	13988	2112						

* SPECIALTY ITEMS

PLOT DATE = Aug 29, 2008 - 12:33:39 PM
 FILE NAME = c:\pwworking\pwworking\PROJECTS\66731\66731.dgn
 PLOT SCALE = 1/8" = 1'-0"
 USER NAME = jprohaska