

**SUMMARY OF QUANTITIES**

CODE #	ITEM	UNIT	QUANTITY	HBP FUNDING 80% FEDERAL 20% STATE ROADWAY 1000	HBP FUNDING 80% FEDERAL 20% STATE SN 029-0066 X081-2A
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	168	168	0
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	68	68	0
20200100	EARTH EXCAVATION	CU YD	899	899	0
20300100	CHANNEL EXCAVATION	CU YD	2210	2210	0
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	215	0	215
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1049	1049	0
25000200	SEEDING, CLASS 2	ACRE	0.29	0.29	0
25000350	SEEDING, CLASS 7	ACRE	0.29	0.29	0
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	25	25	0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	25	25	0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	25	25	0
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.58	0.58	0
25100115	MULCH, METHOD 2	ACRE	0.29	0.29	0
25100630	EROSION CONTROL BLANKET	SQ YD	1015	1015	0
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	116	116	0
28000300	TEMPORARY DITCH CHECKS	EACH	9	9	0
28000400	PERIMETER EROSION BARRIER	FOOT	1305	1305	0
28000500	INLET AND PIPE PROTECTION	EACH	1	1	0
28100207	STONE RIPRAP, CLASS A4	TON	1570	231	1339
28200200	FILTER FABRIC	SQ YD	1901	297	1604
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	242	242	0
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	993	993	0
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	34	34	0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	139	139	0
40600300	AGGREGATE (PRIME COAT)	TON	3	3	0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	99	99	0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	134	134	0
40600990	TEMPORARY RAMP	SQ YD	96	96	0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	117	117	0
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	222	222	0

**SUMMARY OF QUANTITIES**

CODE #	ITEM	UNIT	QUANTITY	HBP FUNDING 80% FEDERAL 20% STATE ROADWAY 1000	HBP FUNDING 80% FEDERAL 20% STATE SN 029-0066 X081-2A
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	44	44	0
44000100	PAVEMENT REMOVAL	SQ YD	536	536	0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	68	68	0
44000400	GUTTER REMOVAL	FOOT	1406	1406	0
44002600	GUTTER OUTLET REMOVAL	FOOT	116	116	0
44004000	PAVED DITCH REMOVAL	FOOT	6	6	0
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1144	1144	0
48203009	HOT-MIX ASPHALT SHOULDERS, 3"	SQ YD	695	695	0
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	301	301	0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	0	1
50105220	PIPE CULVERT REMOVAL	FOOT	34	34	0
50200100	STRUCTURE EXCAVATION	CU YD	402	0	402
50300225	CONCRETE STRUCTURES	CU YD	40	0	40
50300255	CONCRETE SUPERSTRUCTURE	CU YD	153.5	0	153.5
50300260	BRIDGE DECK GROOVING	SQ YD	561	222	339
50300280	CONCRETE ENCASEMENT	CU YD	4.2	0	4.2
50300300	PROTECTIVE COAT	SQ YD	669	222	447
50400735	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 63"	FOOT	599	0	599
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	32040	0	32040
50800515	BAR SPLICERS	EACH	382	0	382
51201610	FURNISHING STEEL PILES HP12X63	FOOT	260	0	260
5120305	DRIVING PILES	FOOT	260	0	260
51203610	TEST PILE STEEL HP12X63	EACH	2	0	2
51204650	PILE SHOES	EACH	12	0	12
51500100	NAME PLATES	EACH	1	0	1
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	34	34	0
54213867	STEEL END SECTIONS 12"	EACH	2	2	0
54213870	STEEL END SECTIONS 15"	EACH	2	2	0

**HAMPTON, LENZINI & RENWICK, INC.**  
 CIVIL & STRUCTURAL ENGINEERS  
 LAND SURVEYORS

3085 STEVENSON DRIVE, SUITE 201  
 SPRINGFIELD, ILLINOIS 62703  
 (217) 546-3400

ELGIN • SPRINGFIELD

PROJECT NUMBER: 12-37-0003-1      DATE: 07/31/08  
 DESIGNED: L.F.S.      CHECKED: S.W.M.      DRAWN: D.T.M.

**SUMMARY OF QUANTITIES**  
**F.A.P. ROUTE 665 (IL 116) OVER LITTLERS CREEK**  
**SECTION (144-B) BR**  
**FULTON COUNTY**