

# SUMMARY OF QUANTITIES

F. A. D. SHEET	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-21-RS-5	EULION	282	9
STA.		TO STA.		
FED. ROAD DIST. NO. 5		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	URBAN				CONSTRUCTION TYPE CODE															
CODE NO	ITEM	UNIT		ROADWAY 1000-2A 90% FED 10% STATE	TUNNEL SIDE WALK REM 1000-2A 100% CITY	TRAFFIC SIGNALS Y031-1F 100% STATE	SIDEWALK 1000-2A 50% STATE 50% CITY																
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	5	5																			
60224071	MANHOLES, TYPE A, 6'-DIAMETER, WITH MEDIAN INLET (604106)	EACH	1	1																			
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1																			
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	14	14																			
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	1	1																			
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	16	16																			
60241800	INLETS, TYPE G-1	EACH	1	1																			
60241900	INLETS, TYPE G-1, SPECIAL	EACH	19	19																			
60242100	INLETS, TYPE G-2	EACH	1	1																			
60255500	MANHOLES TO BE ADJUSTED	EACH	1	1																			
60402210	GRATES, TYPE 8	EACH	1	1																			
60405500	FRAMES AND GRATES (INLET G-1)	EACH	66	66																			
60405600	FRAMES AND GRATES (INLET G-2)	EACH	1	1																			
60500040	REMOVING MANHOLES	EACH	1	1																			
60500050	REMOVING CATCH BASINS	EACH	1	1																			
60500060	REMOVING INLETS	EACH	25	25																			
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	48.1	48.1																			
60602600	CONCRETE GUTTER, TYPE A (MODIFIED)	FOOT	1028	1028																			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	214.5	214.5																			
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	8208.9	8208.9																			
60900515	CONCRETE THRUST BLOCKS	EACH	1	1																			
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	750	750																			
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	23.4		23.4																		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4																			
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	1317	1317																			
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	46	46																			
66700095	PERMANENT SURVEY MARKERS	EACH	23	23																			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10	10																			
67000600	ENGINEER'S FIELD LABORATORY	CAL MO	10	10																			
67100100	MOBILIZATION	L SUM	1	1																			

\* SPECIALTY ITEM