

SUMMARY OF QUANTITIES

F. A. D. DIST.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-21_RS-5	EULTON	282	13
STA.	TO STA.			
FED. ROAD DIST. NO. 5	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES			URB A N					CONSTRUCTION TYPE CODE												
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000-2A 90% FED 10% STATE	TUNNEL SIDE WALK REM 1000-2A 100% CITY	TRAFFIC SIGNALS Y031-1F 100% STATE	SIDEWALK 1000-2A 50% STATE 50% CITY													
XX000321	INLET-MANHOLE, TYPE G-1, 5'-DIAMETER, SPECIAL	EACH	5	5																
XX001672	STORM SEWERS,(POLYVINYL CHLORIDE) SDR 26, 12 INCH	FOOT	225.7	225.7																
XX003570	STORM SEWERS POLYVINYL CHLORIDE, STANDARD DIMENSION RATIO 26, 15"	FOOT	3739.3	3739.3																
XX003571	STORM SEWERS POLYVINYL CHLORIDE, STANDARD DIMENSION RATIO 26, 18"	FOOT	190.1	190.1																
* XX005703	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT, SPECIAL	L SUM	1			1														
* XX005938	SOLAR - POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	1			1														
XX185100	INLET-MANHOLE, TYPE G-1, 4'-DIAMETER	EACH	18	18																
* X0300558	SANITARY SEWER REMOVAL AND REPLACEMENT 8"	FOOT	36		36															
X0301007	INLET-MANHOLE, TYPE G-1, 4'-DIAMETER, SPECIAL	EACH	16	16																
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	177.8	177.8																
X0321473	PIPE ELBOW, 15"	EACH	2	2																
X0325404	INLET-MANHOLE, TYPE G-1, 5' DIAMETER, DOUBLE, SPECIAL	EACH	3	3																
X0322729	MATERIAL TRANSFER DEVICE	TON	4686.4	4686.4																
X0322924	RETAINING WALL REMOVAL	SQ FT	177	177																
X0325279	CLASS SI CONCRETE (MISCELLANEOUS)	CU YD	1.3	1.3																
X0712400	TEMPORARY PAVEMENT	SQ YD	2431	1437	994															
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	2431	1437	994															
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	3433.5	3433.5																
X6020065	INLETS, TYPE G-1, DOUBLE (SPECIAL)	EACH	1	1																
X7030104	WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4 INCH	FOOT	11038	11038																
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 IC	FOOT	245			245														

* SPECIALTY ITEM