

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-2; RS-5	FULTON	282	29
STA.		TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

LOCATION	PIPE CULVERTS CLASS D TYPE 1 15" FOOT	PIPE CULVERTS TYPE 1 RCCP 18" FOOT	PIPE CULVERTS TYPE 1 RCCP 30" FOOT	PIPE CULVERTS TYPE 1 RCCP 36" FOOT	PIPE CULVERTS TYPE 1 RCCP 54" FOOT	PIPE DRAINS 15" FOOT	PRECAST CONCRETE BOX CULVERT 4' X 6' FOOT	CONCRETE COLLAR EACH	METAL END SECTIONS 15" EACH	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18" EACH	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30" EACH
RT 163+75.00 (F.E.)	50								2		
LT 164+00.00 (F.E.)	48								2		
RT 164+42.44 (C.E.)	50								2		
RT 167+75.70 (C.E.)	46								2		
RT 168+48.42 (C.E.)	64								2		
LT 171+24.74 (C.E.)	60								2		
RT 174+94.22 (C.E.)	53								2		
LT 175+55.46 (C.E.)	49								2		
LT 177+28.91 (ALDER ST.)		63								2	
RT 177+46.37 (P.E.)	40								2		
RT 180+36.32 (IL 78 A)		44								2	
LT 180+46.40 (C.E.)	56								2		
LT 181+14 (X-ROAD CULVERT)			9					1			1
RT 181+14 (X-ROAD CULVERT)			7					1			1
LT 185+58.61 (C.E.)	60								2		
LT 186+60.20 (C.E.)	56								2		
RT 187+92.58 (IL 78 A)		64								2	
LT 190+63 (X-ROAD CULVERT)					25						
RT 190+63 (X-ROAD CULVERT)							16	1			
RT 192+25.42 (P.E.)	30								2		
RT 193+81.67 (P.E.)	32								2		
RT 197+78.16 (MARLEE ST.)		78								2	
LT 200+36.89 (C.E.)	45								1		
RT 200+50.56 (P.E.)	28								2		
RT 201+76.01 (C.E.)		61							1		
RT 202+48.85 (C.E.)		70							1		
LT 203+20.06 (C.E.)	41								2		
RT 206+96.96 (C.E.)	40								2		
RT 208+64.21 (C.E.)	54								2		
LT 211+89.88 (F.E.)	40								2		
LT 213+12 (X-ROAD CULVERT)							12	1			
RT 213+12 (X-ROAD CULVERT)							28	1			
RT 216+54.47 (P.E.)	24								2		
LT 220+70 (X-ROAD CULVERT)		10						1		1	
RT 220+70 (X-ROAD CULVERT)		13						1		1	
RT 224+12.77 (C.E.)	47								2		
RT 225+20 (SLOPE)						72.5			1		
LT 225+65 (X-ROAD CULVERT)				20				1			
LT 231+65 (X-ROAD CULVERT)		12								1	
RT 232+10 (DITCH)	21								1		
LT 236+69.04 (P.E.)	30								2		
LT 237+21 (X-ROAD CULVERT)			8					1			
RT 237+21 (X-ROAD CULVERT)			30					1			
RT 238+50 (P.E. + F.E.)	90								2		
RT 239+89.80 (P.E.)	31								2		
RT 242+28.43 (REDWOOD CIR. N)	50									1	
RT 253+91 (S.S. OUTLET 435.5' RT)											1
IL 78 A 8+60 (X-ROAD CULVERT)		40								2	
TOTAL	1235	415	54	20	25	72.5	56	10	53	12	3

PERMANENT SURVEY MARKERS	
LOCATION	EACH
161+00.00 CL (POT)	1
170+75.35 CL (PC)	1
177+28.91 CL (PI ALDER ST.)	1
183+16.86 CL (PT)	1
187+86.02 CL (PC)	1
187+92.58 CL (PI IL 78 A SOUTH)	1
195+48.46 CL (PT)	1
199+96.94 CL (PC)	1
205+38.55 (PI CYPRESS DR. EAST)	1
205+59.15 (PI CYPRESS DR. WEST)	1
211+14.36 CL (PT)	1
221+00.00 CL (POT)	1
226+37.37 CL (PC)	1
229+38.93 9.78' LT (PI OF CURVE)	1
232+39.64 CL (PT)	1
237+94.55 CL (PC)	1
240+84.99 6.89' RT (PI OF CURVE)	1
243+75.00 CL (PT)	1
251+26.60 CL (PI STONEGATE DR.)	1
260+98.43 CL (PI EDMAR DR.)	1
271+96.53 CL (PI WINEGAR DR.)	1
278+33.72 CL (PC)	1
281+81.05 CL (PI BIG CREEK PARK RD.)	1
TOTAL	23

LOCATION	INSPECTION WELLS	STORM SEWER		
		CLASS B TYPE I 4 INCH	CLASS B TYPE I 6 INCH	CLASS B TYPE I 12 INCH
		EACH	FOOT	FOOT
RT 253+43 (S.S. OUTLET)				108
LT 267+34	1		48	
LT 267+51	1			33
LT 268+74	1	25		
LT 269+24	1		7	
RT 270+33	1			38
RT 271+12	1		39	
RT 276+72	1	76		
TOTAL	7	101	94	179

STORM SEWER REMOVAL 12"	
LOCATION	FOOT
252+72 TO 256+14	342
LT 254+47 (ARGONNE DR.)	14
LT 254+76 (ARGONNE DR.)	14
263+62	44
RT 263+62 TO 267+60	398
RT 267+84 (N. PARK DR.)	36
RT 268+03 (N. PARK DR.)	28
LT 272+11 (WINEGAR DR.)	41
LT 275+09 (MA-GRA-BL DR.)	32
LT 275+39 (MA-GRA-BL DR.)	34
LT 278+15 TO 280+11	196
TOTAL	1179

STORM SEWER REMOVAL 18"	
LOCATION	FOOT
LT 280+11 TO 282+49	238
TOTAL	238

STORM SEWER REMOVAL 24"	
LOCATION	FOOT
LT 190+51 TO 190+56	6
LT 190+55	17
RT 268+33 TO 272+49	416
TOTAL	439

STORM SEWER REMOVAL 30"	
LOCATION	FOOT
LT 190+60 TO 190+95	35
TOTAL	35

BOX CULVERT END SECTION			
LOCATION (SIZE)	CULVERT NO. 1	CULVERT NO. 2	CULVERT NO. 3
	EACH	EACH	EACH
RT 190+63 (6 X 4)	1		
LT 213+12 (6 X 4)		1	
RT 213+12 (6 X 4)		1	
LT 227+00 (10 X 7)			1
TOTAL	1	2	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

SCALE: VERT. _____ HORIZ. _____ DATE _____ DRAWN BY _____ CHECKED BY _____

PLOT DATE = 8/19/2008
 FILE NAME = c:\pco\pco\178\beamton\general.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = hughes@illinois.gov