CONTRACT NO. 68285

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-2: RS-5	FULTON	282	30
STA.		TO STA.		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

STORM SEWER PIPES TABLE (1 OF 2)

LOCATION				STORM SEWER CLASS A TYPE 1 12"	STORM SEWER CLASS A TYPE 1 15"	STORM SEWER CLASS A TYPE 2 15"	STORM SEWER CLASS A TYPE 1 18"	STORM SEWER CLASS A TYPE 2 18"	STORM SEWER CLASS A TYPE 2 24"	STORM SEWER CLASS A TYPE 1 30"	STORM SEWER CLASS A TYPE 2 30"	STORM SEWER CLASS A TYPE 3 30"	STORM SEWER (PVC) SDR 26 12"	STORM SEWER (PVC) SDR 26 15"	STORM SEWER (PVC) SDR 26 18"	TRENCH BACKFILL
PIPE NUM.	U/S STR NUM.	D/S STR NUM.	SLOPE (%)	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	CU YD
190+96 TO 190+52			2.0								35					3.2
A1	102	101	1.0											52.2		0
A2	103	102	1.0											129.2		1.9
A3	104	103	0.6											28.9		3.8
A4	105	104	0.6											54.0		7.8
A5	106	105	0.6		73.2											9.7
B2	202	203	0.6											45.9		0.6
B3	203	204	0.6		221.8											0.7
B4	204	205	0.6		35.8											5.8
B5	205	206	1.0											77.3		1.3
B6	206	214	0.6			165.4										22.3
B7	207	208	0.6										89.8			0
B8	209	208	2.0											10.0		1.4
B9	208	210	0.6											190.5		0
B10	211	210	2.0											9.3		1.4
B11	210	212	0.6											49.4		5.8
B12	212	213	0.6											112.1		21.5
B13	213	224	0.6											156.9		0
B14	214	215	0.6			86.9										17.8
B15	215	216	0.6											22.9		6.5
B16	216	217	0.6											29.7		6
B17	217	218	0.6			22.7										7.3
B18	218	220	0.6		105.1											23
B19	219	220	1.0										6.9			1.3
B20	220	221	0.6					169.0								57.8
B21	221	222	0.6								127.2					68.3
B22	223	224	0.6										20.0			1.8
B23	225	224	2.0											5.9		0.8
B24	224	226	0.6											196.9		47
B25	226	227	0.6											14.5		7.5
B26	227	228	0.6											52.2		14.7
B27	228	229	0.6												124.3	96.3
B28	229	221	0.6						50.0							19.9
B29	230	229	0.5											16.6		1.7
B30	241	230	0.6											180.2		0
B31	231	222	0.6		38.1											4.2
B32	232	231	0.6		100.3											7.3
B33	233	232	0.6		4.4											0.7
B34	234	232	0.6		169.2											24.2
B35	235	234	0.6		4.8											0.7
B36	236	234	0.6		28.9											4.1
B37	237	236	0.6		5.1											0.7
B38	238	236	0.6		67.2											8.9
B39	239	238	1.0		6.0											0.6
B40	240	238	0.6		89.0											11.7
B41	242	241	0.6											30.2		12
B42	243	242	0.6											28.4		5.7
B43	244	243	0.6											29.7		6.2
B44	245	244	0.6											166.1		0
B45	246	245	2.0											25.5		0.7
C1	301	302	0.5											108.5		0
C2	303	304	1.1		96.5											11.7
C3	304	305	1.1		65.3											5.4
C4	305	306	1.1		37.5											3.2
SUBTOTAL (THIS PAGE)				0.0	1148.2	275.0	0.0	169.0	50.0	0.0	162.2	0.0	116.7	1823.0	124.3	572.9

MANHOLES TYPE A 7'-DIAMETER TYPE 1 FRAME CLOSED LID

LOCATION	EACH
190+52 58.3' LT	1
TOTAL	1

MANHOLES TYPE A 6'-DIAMETER WITH MEDIAN INLET (604106)

LOCATION	EACH
190+52 78.1' LT	1
TOTAL	1

MANHOLES TO BE ADJUSTED

LOCATION	EACH
196+96 45.2' LT	1
TOTAL	1

FRAMES AND GRATES (INLET G-2)

LOCATION	EACH
231+64 24.0' LT	1
TOTAL	1

GRATES, TYPE 8

LOCATION	EACH
232+12 RT	1
TOTAL	1

METAL END SECTION, 8"

LOCATION	EACH
172+33 40.0' LT	1
TOTAL	1

REMOVING MANHOLES

LOCATION	EACH
LT 190+51	1
TOTAL	1

REMOVING CATCH BASINS

LOCATION	EACH
LT 190+55	1
TOTAL	1

REMOVING INLETS

LOCATION	EACH
LT 190+98 (BUCKEYE ST.)	1
LT 200+15 (SWALE)	1
RT 202+11 (SWALE)	1
LT 232+14 (DITCH)	1
RT 252+72 (CULVERT OUTLET)	1
LT 254+47 (ARGONNE DR.)	1
LT 254+76 (ARGONNE DR.)	1
RT 256+14 (DITCH)	1
LT 263+62 (BANYON DR.)	1
RT 263+62 (GUTTER)	1
RT 267+60 (GUTTER)	1
RT 267+67 (N. PARK DBL INL)	2
RT 268+03 (N. PARK DBL INL)	2
RT 268+33 (DITCH)	1
RT 270+70 (DITCH)	1
LT 271+81 (WINEGAR DR.)	1
LT 272+11 (WINEGAR DR.)	1
RT 272+49 (DITCH)	1
LT 275+09 (MA-GRA-BL DR.)	1
LT 275+39 (MA-GRA-BL DR.)	1
LT 278+15 (DITCH)	1
LT 280+11 (IL 78)	1
LT 280+82 (IL 78)	1
TOTAL	25

PLUG EXISTING CULVERTS

LOCATION	EACH
RT 212+35	1
LT 212+35	1
RT 213+70	1
LT 214+47	1
RT 225+16	1
RT 252+72.58	1
RT 281+98	1
TOTAL	7

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 8/15/2008
FILE NAME = c:\projects\22fulton\general1.dgn
PLOT SCALE = 180.0185 ' / IN.
USER NAME = hudelsonma