

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-2; RS-5	FULTON	282	31
STA.	TO STA.			
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

STORM SEWER PIPES TABLE (2 OF 2)

LOCATION				STORM SEWER CLASS A TYPE 1	STORM SEWER CLASS A TYPE 1	STORM SEWER CLASS A TYPE 2	STORM SEWER CLASS A TYPE 1	STORM SEWER CLASS A TYPE 2	STORM SEWER CLASS A TYPE 2	STORM SEWER CLASS A TYPE 1	STORM SEWER CLASS A TYPE 2	STORM SEWER CLASS A TYPE 3	STORM SEWER (PVC) SDR 26	STORM SEWER (PVC) SDR 26	STORM SEWER (PVC) SDR 26	TRENCH BACKFILL	
PIPE NUM.	U/S STR NUM.	D/S STR NUM.	SLOPE (%)	12"	15"	15"	18"	18"	24"	30"	30"	30"	12"	15"	18"	CU YD	
C5	306	307	0.6		29.6											6.4	
C6	307	308	1.1		117.2											34.4	
C7	308	309	1.1		96.9											11.7	
C8	309	310	1.1		96.1											11.6	
C9	302	312	0.6										57.3			4.3	
C10	311	312	1.0									5.2				0.6	
C11	312	314	0.9										81.4			17.2	
C12	313	314	0.6									5.2				0.7	
C13	314	316	1.0										143.2			22.2	
C14	315	316	0.6									4.5				0.6	
C15	316	318	1.0									5.4				0.7	
C16	317	318	0.6										62.4			9	
C17	318	319	1.1										177.3			21.5	
C18	319	320	0.9													11.7	
C19	310	321	1.1		96.6											6	
C20	321	322	0.6					46.5								9.1	
C21	322	323	1.1					56.7								8.4	
C22	323	324	0.6					58.9								12.5	
C23	324	325	0.8							71.5						22.6	
C24	325	326	0.5							99.8						1.3	
C25	327	326	1.0	6.4												16	
C26	326	328	0.5							78.4						0	
C27	328	337	0.5							72.8						174.5	
C28	320	329	0.9										174.5			21.1	
C29	329	330	1.1										103.5			16.1	
C30	331	330	0.5										50.0			6.2	
C31	330	324	0.5										50.0			5.8	
C32	332	334	0.5									82.3				8.2	
C33	333	334	0.5									6.4				0.8	
C34	334	335	0.5										82.8			56	
C35	335	336	0.5										33.3			13	
C36	336	340	0.5										31.3			7.7	
C37	337	338	0.5							21.7						1.9	
C38	339	338	1.0										89.3			11.8	
C39	340	341	0.5		35.1											12	
C40	341	338	0.5											65.8		18.5	
C41	342	341	0.5										38.6			0	
C42	343	342	1.0										5.6			1.3	
D1	401	402	0.5		30.1											3.6	
D2	402	403	0.5										39.1			7.9	
D3	403	404	0.5										83.5			0	
D4	404	405	0.5										105.7			20.1	
D5	405	412	0.5										57.4			19.5	
D6	406	407	0.5										154.5			10.1	
D7	407	408	0.5		57.3											0	
D8	408	409	0.5		97.0											0	
D9	410	409	0.5										55.3			0	
D10	411	410	1.0		8.9											0.7	
D11	412	413	0.5										196.0			62.1	
D12	413	414	0.5					56.3								19.5	
D13	409	414	0.5					78.5								19.4	
E1	222	501	0.5								126.5					29.7	
E2	501	502	0.5									171.0				0	
E3	502	503	0.5									103.3				0	
SUBTOTAL (THIS PAGE)				6.4	664.8	134.8	162.1	0.0	0.0	344.2	126.5	274.3	109.0	1916.3	65.8	608.4	
SUBTOTAL (PREV. PAGE)				0.0	1148.2	275.0	0.0	169.0	50.0	0.0	162.2	0.0	116.7	1823.0	124.3	572.9	
TOTAL				6.4	1813.0	409.8	162.1	169.0	50.0	344.2	288.7	274.3	225.7	3739.3	190.1	1181.3	

LOCATION	LEFT QUANTITY FOOT	RIGHT QUANTITY FOOT
RT 198+09 TO 200+59	250	
HARVESTER RD.	93.6	
LT 239+76 TO 245+88	558	
LINCOLN RD.	110.8	
LT 246+72 TO 250+83	397.5	
STONEGATE DR.	81.3	
LT 251+70 TO 254+17	227	
ARGONNE DR.	93.7	
LT 255+05 TO 260+51	519	
EDMAR DR.	110.5	
LT 260+43 TO 263+31	161	
BANYON DR.	93.4	
LT 264+35 TO 271+52	656.5	
WINEGAR DR.	97.4	
LT 272+39 TO 274+80	227.5	
MA-GRA-BL DR.	138.4	
LT 275+67 TO 278+10	216	
LINDEN ST.	108.6	
LT 278+99 TO 282+37	311	
REDWOOD CIR. (NORTH)		43.9
RT 242+74 TO 244+98		224
REDWOOD CIR. (SOUTH)		82.7
RT 245+81 TO 248+89		294.5
LAUREL DR.		98
RT 249+75 TO 258+11		735
SUNSET LN.		84.9
RT 258+90 TO 261+62		231.5
VAN DYKE DR.		104.8
RT 262+79 TO 267+38		405
NORTH PARK DR.		96.9
RT 268+32 TO 272+24		345
MIDDLEPARK DR.		140.7
RT 273+31 TO 275+00		155.5
LONGWOOD DR.		108
RT 275+87 TO 281+20		506
BIG CREEK PARK RD.		91.3
RT 282+28 TO 282+38		10
SUBTOTAL (LEFT SIDE)	4451.2	
SUBTOTAL (RIGHT SIDE)		3757.7
TOTAL	8208.9	

LOCATION	QUANTITY FOOT
RT 282+38 TO 282+58	20
REDWOOD CIR.(N)	10
LT 9+32 TO 9+42	
VAN DYKE DR.	85.5
MEDIAN 9+25 TO 9+71	
LONGWOOD DR.	
LT 8+97 TO 9+35	38
RT 8+74 TO 9+35	61
TOTAL	214.5

LOCATION	SQ YD
STAGE I	
RT 263+68 TO 267+67	250
RT 268+02 TO 272+63	678
RT 272+92 TO 275+13	240
STORM SEWER X-INGS	87
SUBTOTAL STAGE I	1255
STAGE II	
LT 273+21 TO 274+85	182
SUBTOTAL STAGE II	182
TOTAL	1437

LOCATION	SQ YD
STAGE I	
RT 263+68 TO 267+67	250
RT 268+02 TO 272+63	678
RT 272+92 TO 275+13	240
STORM SEWER X-INGS	87
SUBTOTAL STAGE I	1255
STAGE II	
LT 273+21 TO 274+85	182
SUBTOTAL STAGE II	182
TOTAL	1437

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

# Schedule of Quantities

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY