CONTRACT NO. 68285

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-2; RS-5	FULTON	282	33
STA.		TO STA.		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

STORM SEWER INLETS TABLE (2 OF 3)

STR NUM	LOCATION	CAST ELEV.	FLOW LINE NORTH	FLOW LINE SOUTH	FLOW LINE EAST	FLOW LINE WEST	MANHOLES TYPE A 4' DIAMETER TYPE 1 FRAME CLOSED LID	MANHOLES TYPE A 4' DIAMETER TYPE 8 GRATE	MANHOLES TYPE A 5' DIAMETER TYPE 1 FRAME CLOSED LID	MANHOLES TYPE A 5' DIAMETER TYPE 8 GRATE	INLET-MANHOLE TYPE G-1 4' DIAMETER	INLET-MANHOLE TYPE G-1 4' DIAMETER (SPECIAL)	INLET-MANHOLE TYPE G-1 5' DIAMETER (SPECIAL)	INLET-MANHOLE TYPE G-1 5' DIAMETER DOUBLE (SPECIAL)	INLETS TYPE A TYPE 8 GRATE	INLETS TYPE A TYPE 11V FRAME AND GRATE	INLETS TYPE B TYPE 8 GRATE	INLETS TYPE G-1	INLETS TYPE G-1 SPECIAL	INLETS TYPE G-1 DOUBLE (SPECIAL)	FRAMES AND GRATES INLET G-1		
																					VANE R	VANE L	DIAG
							EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
230	253+08 32.0' LT	673.78	668.96	668.96	----	----		1															
231	254+24 32.9' RT	673.80	671.02	671.02	----	----											1						
232	255+27 24.0' RT	674.82	671.62	671.62	----	671.62						1										1	
233	255+27 33.5' RT	674.09	----	----	671.65	----									1								
234	257+00 24.0' RT	675.59	672.24	672.30	----	672.24						1										1	
235	257+00 33.9' RT	674.71	----	----	672.27	----									1								
236	257+33 24.0' RT	675.83	672.47	672.81	----	672.47						1											
237	257+33 35.4' RT	674.94	----	----	672.50	----											1						
238	258+05 24.0' RT	676.40	673.21	673.21	----	673.26						1										1	
239	258+05 35.1' RT	675.73	----	----	673.29	----									1								
240	258+97 24.0' RT	676.76	673.74	----	----	----													1			1	
241	254+18 31.8' LT	674.89	670.04	670.04	----	----	1																
242	254+47 53.9' LT	674.33	670.22	670.22	----	----					1												1
243	254+75 53.9' LT	673.85	670.39	670.39	----	----					1												1
244	255+03 33.2' LT	674.09	670.57	670.57	----	----											1						
245	256+72 33.6' LT	674.01	671.57	671.57	----	----											1						
246	257+00 24.0' LT	675.59	672.08	----	----	----						1									1		
301	258+76 33.8' LT	675.88	----	673.44	----	----									1								
302	259+88 33.9' LT	675.34	672.90	672.90	----	----											1						
303	260+48 24.0' RT	676.31	----	673.25	----	----													1		1		
304	261+48 24.0' RT	675.21	672.19	672.19	----	----						1									1		
305	262+12 53.7' RT	674.53	671.49	671.40	----	----					1												1
306	262+50 53.4' RT	674.01	670.99	670.99	----	----					1												1
307	262+79 29.8' RT	674.26	670.81	670.81	----	----	1																
308	264+00 24.0' RT	672.57	669.52	669.52	----	----													1		1		
309	265+00 24.0' RT	671.55	668.45	668.45	----	----													1		1		
310	266+00 24.0' RT	670.49	667.39	667.39	----	----													1		1		
311	260+48 33.6' LT	675.48	----	----	----	673.04									1								
312	260+51 24.0' LT	676.27	672.56	672.56	672.99	----					1												1
313	261+48 34.1' LT	674.28	----	----	----	671.84									1								
314	261+44 24.0' LT	675.26	671.83	671.81	671.81	----					1												1
315	262+94 33.9' LT	672.85	----	----	----	670.41									1								
316	262+94 24.0' LT	673.73	670.38	670.38	670.38	----						1										1	
317	263+41 35.1' LT	672.32	----	----	----	669.88									1								
318	263+50 28.6' LT	673.34	669.94	669.85	669.85	----					1												1
319	264+16 28.6' LT	672.18	669.16	669.07	----	----					1												1
320	266+00 24.0' LT	670.49	667.47	667.36	----	----													1			1	
321	267+00 24.0' RT	669.44	666.33	666.15	----	----													1		1		
322	267+53 28.0' RT	669.08	665.87	665.87	----	----						1											1
323	268+19 28.0' RT	668.56	665.25	665.25	----	----						1											1
SUBTOTAL (THIS PAGE)							2	1	0	0	8	9	0	0	8	0	5	0	7	0	7	6	10

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 8/19/2009
FILE NAME = c:\pw_work\d78santon\generaldgn
PLOT SCALE = 1856.0185 ' / IN.
USER NAME = huckleborne