

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	135W-2; RS-5	FULTON	282	34
STA.		TO STA.		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

STORM SEWER INLETS TABLE (3 OF 3)

STR NUM	LOCATION	CAST ELEV.	FLOW LINE NORTH	FLOW LINE SOUTH	FLOW LINE EAST	FLOW LINE WEST	MANHOLES	MANHOLES	MANHOLES	MANHOLES	INLET-MANHOLE	INLET-MANHOLE	INLET-MANHOLE	INLET-MANHOLE	INLETS	INLETS	INLETS	INLETS	INLETS	INLETS	FRAMES AND GRATES INLET G-1								
							TYPE A 4' DIAMETER TYPE 1 FRAME CLOSED LID	TYPE A 4' DIAMETER TYPE 8 GRATE	TYPE A 5' DIAMETER TYPE 1 FRAME CLOSED LID	TYPE A 5' DIAMETER TYPE 8 GRATE	TYPE G-1 4' DIAMETER	TYPE G-1 4' DIAMETER (SPECIAL)	TYPE G-1 5' DIAMETER (SPECIAL)	TYPE G-1 5' DIAMETER DOUBLE (SPECIAL)	TYPE A TYPE 8 GRATE	TYPE A TYPE 11V FRAME AND GRATE	TYPE B TYPE 8 GRATE	TYPE G-1	TYPE G-1 SPECIAL	TYPE G-1 DOUBLE (SPECIAL)	VANE R	VANE L	DIAG						
							EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH		
324	268+85 24.0' RT	668.35	664.90	664.25	664.26	----							1											1					
325	269+59 24.0' RT	668.05	663.68	663.68	----	----							1											1					
326	270+67 24.0' RT	667.71	663.18	663.18	----	663.69																							
327	270+70 35.5' RT	666.19	----	----	663.75	----									1										2				
328	271+52 35.4' RT	666.59	662.79	662.79	----	----				1																			
329	267+78 24.0' LT	668.81	665.79	665.79	----	----																			1				
330	268+85 24.0' LT	668.35	664.65	664.51	----	664.51						1													1				
331	269+31 48.6' LT	667.20	664.76	----	----	----																							
332	269+78 36.0' LT	666.51	----	664.07	----	----									1														
333	270+63 35.5' LT	666.19	----	----	----	663.75									1														
334	270+67 24.0' LT	667.71	663.66	663.66	663.72	----																			1				
335	271+55 29.1' LT	668.26	663.25	----	663.25	----	1																						
336	271+82 57.5' LT	667.08	----	663.08	----	663.08							1													1			
337	272+25 33.4' RT	666.30	662.43	662.43	----	----				1																			
338	272+48 31.0' RT	667.78	662.32	664.52	662.41	661.53																							
339	273+39 24.0' RT	668.43	665.41	----	----	----																			1				
340	272+09 57.5' LT	667.13	662.92	662.92	----	----							1													1			
341	272+45 36.9' LT	666.40	662.74	663.91	----	662.74																							
342	272+87 34.7' LT	666.54	664.10	----	----	664.10																							
343	272+87 24.0' LT	668.27	----	----	664.16	----																			1				
401	275+10 73.0' LT	667.22	----	664.20	----	----																				1			
402	275+38 73.0' LT	667.13	664.05	----	----	664.05							1													1			
403	275+52 35.7' LT	668.65	----	663.80	663.80	----	1																						
404	276+39 35.0' LT	667.12	663.38	663.38	----	----																							
405	277+48 24.0' LT	667.89	662.85	662.85	----	----																				1			
406	277+48 24.0' RT	667.75	----	664.55	----	----																							
407	279+04 37.3' RT	666.22	663.78	663.41	----	----																							
408	279+63 37.2' RT	665.56	663.12	662.58	----	----																							
409	280+60 36.4' RT	664.54	662.10	661.86	661.86	----																							
410	281+18 36.5' RT	664.54	662.14	----	662.14	----																							
411	281+21 24.0' RT	665.63	----	----	----	662.23																				1			
412	278+09 24.0' LT	667.44	662.56	662.56	----	----																				1			
413	280+11 21.5' LT	666.26	661.58	661.58	----	----																				1			
414	280+82 20.7' LT	665.87	661.30	659.96	----	661.47																				1			
501	253+83 155.0' RT	669.24	----	----	665.45	661.82																							
502	253+83 280.0' RT	664.75	----	----	660.96	652.52																							
SUBTOTAL (THIS PAGE)							2	3	3	2	2	4	2	1	3	1	4	0	8	1	6	7	7						
SUBTOTAL (FIRST PAGE)							2	3	0	3	8	3	3	2	3	0	7	1	4	0	5	5	13						
SUBTOTAL (SECOND PAGE)							2	1	0	0	8	9	0	0	8	0	5	0	7	0	7	6	10						
SUBTOTAL																													
TOTAL							6	7	3	5	18	16	5	3	14	1	16	1	19	1									66

PLOT DATE = 8/10/2008
 FILE NAME = c:\pwworkspace\117800000\gen\all.dwg
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = hnd110000

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

Schedule of Quantities

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____