

SUMMARY OF QUANTITIES				ROADWAY FAP 645 80% FEDERAL 20% STATE	STRUCTURE SN.062-0072 80% FEDERAL 20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				1000-2A	X081-2A
51602000	PERMANENT CASING	FOOT	15.5		15.5
51604000	DRILLED SHAFT IN ROCK	CU YD	20.6		20.6
54215547	METAL END SECTIONS 12"	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	84		84
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	4	4	
60100945	PIPE DRAINS 12"	FOOT	69	69	
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	28	28	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	161.2		161.2
60602500	CONCRETE GUTTER, TYPE A	FOOT	100	100	
60900115	TYPE B INLET BOX, STANDARD 609001	EACH	2	2	
60900515	CONCRETE THRUST BLOCKS	EACH	2	2	
* 63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	500	500	
* 63100085	TRAFFIC BARRIER TERMINAL TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3	
63200310	GUARDRAIL REMOVAL	FOOT	660	660	
* 63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	59	59	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	11	11	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	227	227	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2768	2768	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1338	1338	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	800	800	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	800	800	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2768	2768	
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	4	4	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3	
78300100	PAVEMENT MARKING REMOVAL	SQ. FT	913	913	
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	197	197	
X0321781	MECHANICAL SPLICE	EACH	40		40
X0322584	REVTMENT MAT REMOVAL	SQ YD	106	106	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ. FT	904	80	824
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	24		24
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0022800	FENCE REMOVAL	FOOT	1010	1010	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0037300	PAVEMENT GROOVING	SQ YD	334	334	
Z0038700	PERMANENT BENCH MARKS	EACH	1	1	
Z0076600	TRAINEES	HOUR	500		500
X0326211	MACRO SYNTHETIC FIBERS FOR BRIDGE SUPERSTRUCTURE CONCRETE	POUND	600		600

*SPECIALTY ITEM ■ Y080 (80% FED 20% STATE)

FILE NAME =
#FILEABBREV#
THE UPCHURCH GROUP, INC.

USER NAME = brucebm	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 2.0370' / IN.	CHECKED -	REVISED -
PLOT DATE = 9/13/2008 #TIME#	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES
ILLINOIS ROUTE 17 OVER SENACHWINE CREEK**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
645	(105BR)BR	Marshall	71	4
CONTRACT NO. 68479			FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT	