

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	Y007 80/20 FED/STATE
20200100	EARTH EXCAVATION	CU YD	209	209
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	38	38
20400800	FURNISHED EXCAVATION	CU YD	358	358
20700110	POROUS GRANULAR EMBANKMENT	TON	140	140
20800150	TRENCH BACKFILL	CU YD	40	40
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	171	171
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	257	257
25000210	SEEDING, CLASS 2A	ACRE	0.75	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	<i>POUND</i>	68	68
25000500	PHOSPHORUS FERTILIZER NUTRIENT	<i>POUND</i>	68	68
25000600	POTASSIUM FERTILIZER NUTRIENT	<i>POUND</i>	68	68
25100115	MULCH, METHOD 2	ACRE	0.75	0.75
25100630	EROSION CONTROL BLANKET	SQ YD	403	403
28000250	TEMPORARY EROSION CONTROL SEEDING	<i>POUND</i>	100	100
28000300	TEMPORARY DITCH CHECKS	EACH	8	8
28000400	PERIMETER EROSION BARRIER	FOOT	584	584
28000500	INLET AND PIPE PROTECTION	EACH	2	2
28100209	STONE RIPRAP, CLASS A5	TON	118	118
28200200	FILTER FABRIC	SQ YD	188	188
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	103	103
35501450	HOT - MIX ASPHALT BASE COURSE	TON	42	42
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.8	0.8
40600300	AGGREGATE (PRIME COAT)	TON	2	2
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	450	450
40600990	TEMPORARY RAMP	SQ YD	126	126
40603080	HOT - MIX ASPHALT BINDER COURSE, IL - 19.0, N50	TON	200	200