

EARTH WORK SCHEDULE					
LOCATION	EARTH EXCAV.	ADJUSTED FOR SHRINKAGE*	EMBANKMENT	TOPSOIL EXC & PLAC	EARTH BALANCE FURNISHED EXC(-) WASTE(+)
	CU YD	CU YD	CU YD	CU YD	CU YD
RT. STA. 723+25 TO STA. 724+00	10.2	7.7	3.3	14.3	-9.9
LT. STA. 723+25 TO STA. 724+00	6.9	5.2	7.0	14.6	-16.4
RT. STA. 724+00 TO STA. 724+71	11.1	8.3	47.9	27.4	-67.0
LT. STA. 724+00 TO STA. 724+71	24.0	18.0	29.5	27.7	-39.2
RT. STA. 724+71 TO STA. 724+79	1.3	1.0	7.2	3.2	-9.4
LT. STA. 724+71 TO STA. 724+79	4.8	3.6	9.8	3.1	-9.3
RT. STA. 724+79 TO STA. 725+00	6.2	4.7	8.3	9.0	-12.7
LT. STA. 724+79 TO STA. 725+00	19.2	14.4	27.8	8.3	-21.7
RT. STA. 725+00 TO STA. 725+15	4.6	3.5	7.3	6.5	-10.3
LT. STA. 725+00 TO STA. 725+15	13.8	10.4	11.4	5.9	-6.9
RT. STA. 725+15 TO STA. 725+43	9.5	7.1	17	11.0	-20.9
LT. STA. 725+15 TO STA. 725+43	14.0	10.5	16.6	10.7	-16.8
RT. STA. 725+43 TO STA. 726+00	17.5	13.1	19.5	20.9	-27.3
LT. STA. 725+43 TO STA. 726+00	12.7	9.5	21	21.2	-32.6
RT. STA. 726+00 TO STA. 727+00	30.0	22.5	10.7	35.9	-24.1
LT. STA. 726+00 TO STA. 727+00	21.8	16.4	13.1	35.6	-32.3
RT. STA. 727+00 TO STA. 727+05	0.9	0.7	0.1	0.9	-0.3
LT. STA. 727+00 TO STA. 727+05	0.7	0.5	0.1	0.9	-0.4
TOTAL	209	157	258	257	-358

\*SHRINKAGE FACTOR ASSUMED TO BE 25%

FERTILIZER NUTRIENT SCHEDULE AND APPLICATION RATE			
LOCATION	NITROGEN	PHOSPHORUS	POTASSIUM
	LB	LB	LB
STA. 723+25 TO STA. 727+05	68	68	68
TOTAL	68	68	68
APPLICATION RATE	90 LB/ACRE EACH NUTRIENT		

TOPSOIL SURVEY (FOR INFORMATION ONLY)			
LOCATION	FORESLOPE	DITCH BOTTOM	BACKSLOPE
	INCH	INCH	INCH
LT. STA. 724+71	10	12	12
RT. STA. 724+71	8	10	10
LT. STA. 725+00	-	-	12
RT. STA. 725+00	8	-	8
LT. STA. 725+43	8	12	18
RT. STA. 725+43	8	-	16

STORM SEWER SCHEDULE			
LOCATION*	STORM SEWER CL A, TY 1 24"	FIELD TILE JUNC. VAULT 4' DIA.	TRENCH BACKFILL
	FOOT	EACH	CU YD
55' LT. STA. 724+79		1	
55' LT. STA. 724+79 TO 38' RT. STA. 725+33	106		13
38' RT. STA. 725+33		1	
TOTAL	106	2	13

\*STATIONS ARE APPROXIMATE AND MAY BE ADJUSTED IN THE FIELD

RAISED REFLECTIVE PAVEMENT MARKER	
LOCATION	EACH
☉ STA. 723+25 TO STA. 727+05	5
TOTAL	5

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
☉ STA. 723+25 TO STA. 727+05	5
TOTAL	5

TRAFFIC CONTROL AND PROTECTION (SPECIAL)	
LOCATION	L.SUM
JOBSITE	1
TOTAL	1

CONSTRUCTION LAYOUT	
LOCATION	L. SUM
JOBSITE	1
TOTAL	1