

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698	126BR	WOODFORD	56	3
STA. 519+62.00 TO STA. 523+13.00				
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY (80% Fed.-20% St.)	ROADWAY 1000-2A Woodford Co.	S.N. 102-0082 X020-2A WOODFORD
20101100	TREE TRUNK PROTECTION	EACH	10	10	
20200100	EARTH EXCAVATION	CU YD	94	94	
20300100	CHANNEL EXCAVATION	CU YD	741	741	
20400800	FURNISHED EXCAVATION	CU YD	372	372	
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	111		111
21101615	TOPSOIL FURNISH ^{AND} PLACE, 4"	SQ YD	852	852	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	44	44	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	44	44	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	44	44	
25001700	SEEDING, CLASS 3 (MODIFIED)	ACRE	0.5	0.5	
25100115	MULCH, METHOD 2	ACRE	0.5	0.5	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	1048	1048	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	48	48	
28000400	PERIMETER EROSION BARRIER	FOOT	726	726	
28000500	INLET AND PIPE PROTECTION	EACH	5	5	
28100109	STONE RIPRAP, CLASS A5	SQ. YD.	800		800
28200200	FILTER FABRIC	SQ. YD.	970		970
35101400	AGGREGATE BASE COURSE, TYPE B	TON	18	18	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	0.41	0.41	
40600300	AGGREGATE (PRIME COAT)	TON	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	416	416	
40600990	TEMPORARY RAMP	SQ YD	58	58	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	80	80	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	7	7	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY (80% Fed.-20% St.)	ROADWAY 1000-2A Woodford Co.	S.N. 102-0082 X020-2A WOODFORD
42001400	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ YD	270	270	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	54	54	
44000100	PAVEMENT REMOVAL	SQ YD	268	268	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	438	438	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	51	51	
44000500	^{COMBINATION AND} CURB CUTTER REMOVAL	FOOT	629	629	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	51	51	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50200100	STRUCTURE EXCAVATION	CU YD	362		362
50300225	CONCRETE STRUCTURES	CU YD	132.6		132.6
50300255	CONCRETE SUPERSTRUCTURES	CU YD	206.3		206.3
50300260	BRIDGE DECK GROOVING	SQ. YD.	250		250
50300280	CONCRETE ENCASEMENT	CU YD	12.2		12.2
50300300	PROTECTIVE COAT	SQ. YD.	470		470
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	46400		46400
50800515	BAR SPLICERS	EACH	213		213
51201610	FURNISHING STEEL PILES HP12X63	FOOT	1625		1625
51202305	DRIVING PILES	FOOT	1625		1625
51203610	TEST PILE STEEL HP 12X63	EACH	2		2
51205200	TEMPORARY SHEET PILING	SQ. FT.	726		726
51500100	NAME PLATES	EACH	1		1
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1	1	

△ REVISED 10/14/08

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 F.A.P. 698
 SECTION 126BR
 WOODFORD COUNTY
 SCALE: VERT. DRAWN BY : GSJ
 HORIZ. CHECKED BY : KRG
 DATE : 10/31/07

PLT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#