

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
698	126BR	WOODFORD	56 4
STA. 519+62.00		TO STA. 523+13.00	
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY (80% Fed.-20% St.)	ROADWAY 1000-2A Woodford Co.	S.N. 102-0082 X020-2A WOODFORD
55100700	STORM SEWER REMOVAL 15"	FOOT	20	20	
55101600	STORM SEWER REMOVAL 36"	FOOT	20	20	
59100100	GEOCOMPOSITE WALL DRAIN	SQ. YD.	250		250
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	147		147
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
60260100	INLET TO BE ADJUSTED	EACH	7	7	
60605000	COMBINATION AND CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	450	450	
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	3	3	
* 63100215	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	4	4	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	8	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
66700605	PERMANENT SURVEY TIES	EACH	4	4	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	351	351	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3180	3180	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	52	52	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1163	1163	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	324	324	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNITS	TOTAL QUANTITY (80% Fed.-20% St.)	ROADWAY 1000-2A Woodford Co.	S.N. 102-0082 X020-2A WOODFORD
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	284	284	
* 78001110	PAINT PAVEMENT MARKING-LINE 4"	FOOT	1630	1630	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	1		1
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	4	4	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	20	20	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	20	20	
X0301512	GUARDRAIL AGGREGATE EROSION CONTROL	TON	146	146	
X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	2	2	
X0325569	TEMPORARY BRIDGE TRAFFIC SIGNALS RESIDENTIAL APPROACH	EACH	3	3	
X0325670	CONCRETE BRIDGE RAIL SIDEWALK MOUNTED	FOOT	161		161
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75,N50	TON	18.1	18.1	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 1	EACH	1		1
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION-LOCATION 2	EACH	1		1
* X6310190	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED), MODIFIED	EACH	1	1	
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14	14	
X7016500	TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)	EACH	1	1	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1		1
Z0076600	TRAINEES	hour	500	500	

● Y080 80% FED 20% STATE

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

F.A.P. 698
SECTION 126BR
WOODFORD COUNTY

SCALE: VERT.
HORIZ.
DATE: 10/31/07

DRAWN BY: GSJ
CHECKED BY: KRJ