

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
698	126BR	WOODFORD	56	8
STA. 519+62.00		TO STA. 523+13.00		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

DRAINAGE ITEMS									
CODE NO.	54213660	54213681	550A0360	550A0160	55100700	55101600	60255500	60260100	X0322054
LOCATION	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	STORM SEWERS, CLASS A, TYPE 2 15"	STORM SEWERS, CLASS A, TYPE 1 36"	STORM SEWER REMOVAL 15"	STORM SEWER REMOVAL 36"	MANHOLES TO BE ADJUSTED	INLET TO BE ADJUSTED	REMOVAL OF PRECAST FLARED END SECTION
IL 89	EACH	EACH	FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH
STA. 521+32.00, 32' RT.	1								
STA. 521+72.10, 35' LT.		1							
STA. 521+12.00 TO STA. 521+32.00 RT.			20		20				
STA. 521+72.10 TO STA. 521+12.04 LT.				20		20			
STA. 520+38.92, 28.8' LT.							1		
STA. 522+29.01, 35.8' LT.							1		
STA. 519+86.81, 33.9' RT.								1	
STA. 520+17.97, 13.9' LT.								1	
STA. 520+37.49, 18.2' RT.								1	
STA. 522+77.65, 13.9' RT.								1	
STA. 522+78.79, 14.1' LT.								1	
STA. 522+91.28, 13.9' RT.								1	
STA. 522+91.27, 14.1' LT.								1	
STA. 521+32.00, 32' RT.									1
STA. 521+72.10, 35' LT.									1
TOTAL	1	1	20	20	20	20	2	7	2

CODE NO. 66600105

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS

LOCATION	EACH
STA. 521+25.00, 40.00' RT.	1
STA. 521+73.00, 50.00' RT.	1
STA. 523+05.00, 50.00' RT.	1
STA. 523+05.00, 40.00' RT.	1
STA. 521+50.00, 40.00' LT.	1
STA. 521+50.00, 45.00' LT.	1
STA. 522+75.00, 45.00' LT.	1
STA. 523+00.00, 40.00' LT.	1
TOTAL	8

CODE NO. 78201000

TERMINAL MARKER - DIRECT APPLIED

LOCATION	EACH
RT. STA. 520+51	1
LT. STA. 520+11	1
RT. STA. 522+93	1
LT. STA. 522+78	1
TOTAL	4

CODE NO. 67100100

MOBILIZATION

LOCATION	L SUM
JOBSITE	1
TOTAL	1

CODE NO. 78100105

RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)

LOCATION	EACH
STA. 521+47.00 (SN 102-0082)	1
TOTAL	1

TEMPORARY PAVEMENT MARKING - LINE

LOCATION	70300280	70300220		
	24"	4"		
	STOP BAR	INSIDE EDGE	OUTSIDE EDGE	CENTER LINE
STAGE I	FOOT	FOOT	FOOT	FOOT
STA. 517+42.41	13			
STA. 517+42.41 TO STA. 525+21.62		775	775	
STA. 525+21.62	13			
STAGE II				
STA. 517+42.41	13			
STA. 517+42.41 TO STA. 525+21.55		775	775	
STA. 525+21.55	13			
RESURFACING				
STA. 519+62.00 TO STA. 523+13.00				80
SUB-TOTAL	52	1550	1550	80

CODE NO. 70100405

TRAFFIC CONTROL AND PROTECTION, STANDARD 701321

LOCATION	EACH
STA. 502+47.41 TO STA. 517+47.41	1
TOTAL	1

CODE NO. 70400100

TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
STA. 519+97.62 TO STA. 520+57.62	61
STA. 520+57.62 TO STA. 522+57.62	199
STA. 522+57.62 TO STA. 523+20.76	64
TOTAL	324

70301000

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	STOP BAR	INSIDE EDGE	OUTSIDE EDGE	CENTER LINE
	SO FT	SO FT	SO FT	SO FT
STAGE I				
STA. 517+42.41	26			
STA. 517+42.41 TO STA. 525+21.62		258	258	
STA. 525+21.62	26			
STAGE II				
STA. 517+42.41	26			
STA. 517+42.41 TO STA. 525+21.55		258	258	
STA. 525+21.55	26			
RESURFACING				
STA. 519+62.00 TO STA. 523+13.00				27
SUB-TOTAL	104	516	516	27
TOTAL	1163			

CODE NO. 78200420

GUARDRAIL MARKERS, TYPE B

LOCATION	EACH
RT. STA. 521+21 TO STA. 521+97	2
LT. STA. 521+07 TO STA. 522+83	2
TOTAL	4

CODE NO. 66700205

PERMANENT SURVEY MARKERS, TYPE I

LOCATION	EACH
JOBSITE	1
TOTAL	1

CODE NO. X7015005

CHANGEABLE MESSAGE SIGN

LOCATION	CAL DA
JOBSITE	14
TOTAL	14

CODE NO. 70103815

TRAFFIC CONTROL SURVEILLANCE

LOCATION	CAL. DA
JOBSITE	60
TOTAL	60

CODE NO. 70300100

SHORT-TERM PAVEMENT MARKING

LOCATION	FOOT
STA. 519+62 TO STA. 523+13	351
TOTAL	351

CODE NO. 70400200

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
STA. 519+94.48 TO STA. 520+57.62	64
STA. 520+57.62 TO STA. 522+47.40	190
STA. 522+47.40 TO STA. 522+76.55	30
TOTAL	284

CODE NO. 78200410

GUARDRAIL MARKERS, TYPE A

LOCATION	EACH
RT. STA. 520+51 TO STA. 521+21	2
LT. STA. 520+11 TO STA. 521+07	2
LT. STA. 521+83 TO STA. 522+78	2
RT. STA. 521+97 TO STA. 522+93	2
TOTAL	8

CODE NO. 66700305

PERMANENT SURVEY MARKERS, TYPE II

LOCATION	EACH
STA. 520+01.16, 0.00' LT.	1
STA. 523+71.53, 0.45' LT.	1
TOTAL	2

CODE NO. X7016500

TEMPORARY BRIDGE TRAFFIC SIGNALS (SPECIAL)

LOCATION	EACH
JOBSITE	1
TOTAL	1

CODE NO. Z0030350

IMPACT ATTENUATORS, RELOCATE TEMP (NON-REDIRECTIVE), TL3

LOCATION - STAGE 2	EACH
STA. 519+94.48	1
STA. 522+76.55	1
TOTAL	2

CODE NO. 70100460

TRAFFIC CONTROL AND PROTECTION, STANDARD 701306

LOCATION	L SUM
JOBSITE	1
TOTAL	1

CODE NO. X0301512

GUARDRAIL AGGREGATE EROSION CONTROL

LOCATION	TON
RT. STA. 520+24.75 TO STA. 521+20.73	27
LT. STA. 519+98.09 TO STA. 521+03.45	36
RT. STA. 522+01.39 TO STA. 523+07.76	39
LT. STA. 521+84.21 TO STA. 523+06.00	44
TOTAL	146

CODE NO. 78100100

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	SPACING	EACH
	FOOT	FOOT
STA. 519+62.00 TO STA. 523+13.00	80 FT	4
TOTAL	4	

CODE NO. 67000400

ENGINEER'S FIELD OFFICE, TYPE A

LOCATION	CAL MON.
JOBSITE	8
TOTAL	8

REVISIONS

NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

F.A.P. 698 SECTION 126BR WOODFORD COUNTY

SCALE: VERT. DATE: 10/31/07 DRAWN BY: CSJ CHECKED BY: KRG