

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	DOUGLAS	76	6

\* (15,21-25,21-26,27)RS-1

# SUMMARY OF QUANTITIES

LOCATION OF WORK:	I-57	I-57	I-57	I-57
	DOUGLAS	DOUGLAS	DOUGLAS	DOUGLAS
	COUNTY	COUNTY	COUNTY	COUNTY
	Sta. 1386+91.00	SN 021-0001	SN 021-0005 &	SN 021-0008
	to Sta. 547+00		SN 021-0006	
	RURAL	RURAL	RURAL	RURAL
	90% FED	90% FED	90% FED	90% FED
	10% STATE	10% STATE	10% STATE	10% STATE
CONSTRUCTION TYPE CODE:	1000-2A	SFTY-2A	SFTY-2A	SFTY-2A

CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	17,374.0	17,374.0
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	81,709.0	81,709.0
44001005	HOT-MIX ASPHALT SURFACE REMOVAL	SQ YD	270.0	270.0
44002805	ISLAND REMOVAL	SQ FT	1,612.0	1,612.0
44200523	CLASS A PATCHES, TYPE IV, 7 INCH	SQ YD	4,400.0	4,400.0
44200549	CLASS A PATCHES, TYPE I, 10 INCH	SQ YD	24.0	24.0
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	214.0	214.0
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SQ YD	40.0	40.0
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	27.0	27.0
44200573	CLASS A PATCHES, TYPE I, 12 INCH	SQ YD	20.0	20.0
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	55.0	55.0
44213000	PATCHING REINFORCEMENT	SQ YD	4,780.0	4,780.0
44213200	SAW CUTS	FOOT	16,032.0	16,032.0
44400100	FIBER GLASS FABRIC REPAIR SYSTEM	SQ YD	2,274.0	2,274.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	767.0	767.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	34,843.0	34,843.0
48203105	HOT-MIX ASPHALT SHOULDERS, SPECIAL	TON	660.0	660.0
50102400	CONCRETE REMOVAL	CU YD	15.9	15.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	15.9	15.9
50300300	PROTECTIVE COAT	SQ YD	58.0	58.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2,590.0	2,590.0
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1.0	1.0
60622354	CONCRETE MEDIAN, TYPE SM-6 (DOWELLED)	SQ FT	1,645.0	1,645.0
* 63500105	DELINEATORS	EACH	234.0	234.0
63500120	DELINEATOR REMOVAL	EACH	234.0	234.0
64200105	SHOULDER RUMBLE STRIP	FOOT	211,477.0	211,477.0
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	9.0	9.0

\* SPECIALTY ITEMS

SHEET 2 OF 4

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
 F.A.I. ROUTE 57  
 SECTION (15,21-25,21-26,27)RS-1  
 DOUGLAS COUNTY

SCALE: N/A  
 DATE: 08-12-08

DRAWN BY: JP  
 CHECKED BY: KD

PLOT DATE = 8/21/2008  
 FILE NAME = c:\pwork\mca\j201005\081208\70465cover.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = ahshahum