CONTRACT NO. 70517

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6406	1(BR-2)	MCLEAN	74	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

	PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	ACM ROADWAY STP TWO-LANE URBAN ROADWAY 80% FEDERAL 20% STATE 1000-2A	ACBRM STRUCTURE HBP TWO-LANE URBAN ROADWAY 80% FEDERAL 20% STATE X071-2A
	60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	766	766	0
	60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	161	161	0
	63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	262.5	262.5	0
•	63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	3	3	0
•	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	0
•	63100215	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	1	1	0
	63200310	GUARDRAIL REMOVAL	FOOT	409	409	0
•	63300725	STEEL PLATE BEAM GUARD RAIL (SHORT RADIUS)	FOOT	112.5	112.5	0
	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	2	2	0
	66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	1	1	0
	67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	2	3
	67100100	MOBILIZATION	L SUM	1	0.5	0.5
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	0.5	0.5
•	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5076	5076	0
•	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	30	30	0
•	78200405	GUARDRAIL MARKERS	EACH	8	8	0
•	78200500	BARRIER WALL MARKERS	EACH	4	0	4
•	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	0
	X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2	2	0
	X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	0	1
	X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	0	1
	X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28	28	0
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	0
•	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	52	0	52
	Z0037300	PAVEMENT GROOVING	SQ YD	250	250	0
	Z0038700	PERMANENT BENCH MARKS	EACH	1	1	0

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY STP TWO-LANE URBAN ROADWAY 80% FEDERAL 20% STATE 1000-2A	STRUCTURE HBP TWO-LANE URBAN ROADWAY 80% FEDERAL 20% STATE X071-2A

• DENOTES SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
SHEET 2 OF 2

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY

PLOT DATE = 8/25/2008
FILE NAME = s:\projects\u563786 (v8)\1.2\1.2827 submittal\quantitiessummary.dgn
PLOT SCALE = 42.353 ' / IN.
USER NAME = ekulcsa

BLANK, WESSELINK, COOK & ASSOCIATES ENGINEERS - CONSULTANTS DECATUR, ILLINOIS

F.A.U. 6406 (US RTE. 150) SECTION 1(BR-2)

MCLEAN COUNTY