

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 730
U.S. 51 BR
(CENTER ST.)
&
EMERSON ST.
100% STATE
Y031-1F
QUANTITY

FAP 730
U.S. 51 BR
(MAIN ST.)
&
EMERSON ST.
100% STATE
Y031-1F
QUANTITY

FAP 730
U.S. 51 BR
(MAIN ST.)
&
WOOD ST.
100% STATE
Y031-1F
QUANTITY

CONSTRUCTION TYPE CODE:

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	Y031-1F QUANTITY	Y031-1F QUANTITY	Y031-1F QUANTITY
X8774420	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 38 FT. AND 40 FT.	EACH	1.0	1.0		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	442	111	198	133.0
42400610	TEMPORARY SIDEWALK	SQ FT	297.0	97.0	100.0	100.0
44000600	SIDEWALK REMOVAL	SQ FT	373	97.0	156	120.0
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	19.0		19.0	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - G.24	FOOT	15		15	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	14.0		14.0	
67100100	MOBILIZATION	L SUM	1.0	.4	.3	.3
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	.4	.3	.3
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0	.4	.3	.3
80500100	SERVICE INSTALLATION, TYPE A	EACH	3.0	1.0	1.0	1.0
81012300	CONDUIT IN TRENCH, 1" DIA., PVC	FOOT	109	30	42	37
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	742.0	235.0	366.0	141.0
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	255	83	95	77.0
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	85.0	10.0	47.0	28.0
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	41.0	19.0	22.0	
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	16.0			16.0
81013100	CONDUIT IN TRENCH, 5" DIA., PVC	FOOT	8.0	3.0	2.0	3.0
81021570	CONDUIT, AUGERED 3" DIA., PVC	FOOT	432.0	200.0	151.0	81.0
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	127.0		70.0	57.0
81030100	CONDUIT SPLICE	EACH	1.0		1.0	
81400100	HANDHOLE	EACH	130	4.0	6.0	3.0
81400300	DOUBLE HANDHOLE	EACH	3.0	1.0	1.0	1.0
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1,256	380	574	302
83057180	LIGHT POLE, WOOD, 35 FOOT, CLASS 4	EACH	1.0		1.0	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	620.0	620.0		
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,073.0	125.0	540.0	408.0
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,498.0	699.0	1,053.0	746.0
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2,242.0	811.0	692.0	739.0
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3,271	892	1,842	537
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	200		200	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	198		198	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	40		40	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	261		261	

FILE NAME = c:\projects\4570730\emerson_street.dgn	USER NAME = biggsrd	DESIGNED - RDB	REVISD -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	F.A.P. RTE. 730	SECTION (BCS)TS(62Z)TS(62Z-2)TS	COUNTY MCLEAN	TOTAL SHEETS 14	SHEET NO. 3
PLOT SCALE = 48,0000' / IN.		CHECKED -	REVISD -								CONTRACT NO. 70730				
PLOT DATE = 8/27/2008		DATE -	REVISD -								FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				