

SUMMARY OF QUANTITIES				ROADWAY FAP 315 80% FEDERAL 20% STATE	STRUCTURE S.N. 054-0023 80% FEDERAL 20% STATE
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION 1000-2A	TYPE CODE X080-2A
20100500	TREE REMOVAL, ACRES	ACRE	0.7	0.7	
20200100	EARTH EXCAVATION	CU YD	160	160	
20201450	SUB-BASE GRANULAR MATERIAL, TYPE A	CU YD	154	154	
20400805	FURNISHED EXCAVATION, SPECIAL	CU YD	9380	9380	
25000200	SEEDING, CLASS 2	ACRE	1.0	1.0	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2.0	2.0	
25100115	MULCH, METHOD 2	ACRE	1.0	1.0	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
28000400	PERIMETER EROSION BARRIER	FOOT	169	169	
28001000	AGGREGATE (EROSION CONTROL)	TON	15	15	
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	523	523	
28200200	FILTER FABRIC	SQ YD	784	784	
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	778	778	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.65	0.65	
40600300	AGGREGATE (PRIME COAT)	TON	3.35	3.35	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	227	227	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	105	105	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	17	17	
44000100	PAVEMENT REMOVAL	SQ YD	113	113	
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	76	76	
48203005	HOT-MIX ASPHALT SHOULDERS, 2"	SQ YD	571	571	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50105220	PIPE CULVERT REMOVAL	FOOT	62	62	

SUMMARY OF QUANTITIES				ROADWAY FAP 315 80% FEDERAL 20% STATE	STRUCTURE S.N. 054-0023 80% FEDERAL 20% STATE
CODE NO.	SUMMARY OF QUANTITIES PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION 1000-2A	TYPE CODE X080-2A
54203601	PIPE CULVERTS, TYPE 5 RCCP 36"	FOOT	206	206	
54215436	CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 36"	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	360	360	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	8	8	
67100100	MOBILIZATION	L SUM	1	1	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	840	840	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	5	5	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	3	3	
X6028300	INLETS TO BE REMOVED, SPECIAL	EACH	2	2	
XX005369	TRAFFIC CONTROL & PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	56		56

*Specialty Items

FILE NAME =
0672A99-S00.dgn

USER NAME = loughlinc1
DESIGNED -
DRAWN -
CHECKED -
DATE -
PLOT SCALE = 2.0000' / IN.
PLOT DATE = Sep-10-2008 10:05:28AM

DESIGNED -
DRAWN -
CHECKED -
DATE -
REVISED -
REVISED -
REVISED -
REVISED -



Allen Henderson & Associates, Inc.
Civil and Structural Engineers Springfield, IL.
62703 Phone: (217)544-8033 IL Design Firm
No. 184-001907

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 315 SECTION (116)I-4 COUNTY LOGAN TOTAL SHEETS 20 SHEET NO. 3
CONTRACT NO. 72A99
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

Rev