

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES

LOCATION OF WORK				<i>100% STATE</i>
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	Y030-1E
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1
81020500	CONDUIT PUSHED, 2" DIA., INTERMEDIATE METAL	FOOT	93	93
81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	260	260
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	147	147
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	2	2
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	1	1
83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT	EACH	2	2
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	2	2
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	8	8