F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
609	***	ST. CLAIR	350	19
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

***76RS-3, 76-2BR-2I

DESIGN		
INT.	DATE	REASON

PLOTS & CHECKS			
INT.	DATE	NO.	REASON

CHECKS		
INT.	DATE	REASON

PAVEMENT, CURB AND GUTTER, SIDEWALK AND RIPRAP REMOVAL SCHEDULE

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	REMOVAL OF EXISTING RIPRAP	CURB REMOVAL	GUTTER REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL
	SQ. YD.	SQ. YD.	SQ. YD.	SQ. YD.	SQ YD	FOOT	FOOT	FOOT	SQ FT
IL 163									
STA. 9+74 TO STA. 10+36 (INTERSECTION)	372								
STA. 10+17.88, 30.00' RT. TO STA. 10+84.25, 17.46' RT.						79			
STA. 10+18.37, 27.21' RT. TO STA. 10+85.60, 17.46' RT.									442
STA. 10+18.38, 22.94' LT. TO STA. 10+45.91, 22.58' LT.									131
STA. 10+19.96, 17.76' LT. TO STA. 12+75.24, 23.91' LT.						263			
STA. 10+20.40, 18.15' LT. TO STA. 14+00.00, 13.00' LT.				211					
STA. 10+20.94, 34.48' LT. TO STA. 10+27.52, 13.98' LT.						27			
STA. 10+25.20, 15.32' RT. TO STA. 14+00.00, 13.00' RT.				263					
STA. 10+36 TO STA. 23+75	3535								
STA. 11+35.42, 23.13' LT. TO STA. 11+47.64, 23.40' LT.									45
STA. 11+39.04, 24.43' RT. TO STA. 11+49.13, 24.40' RT.									41
STA. 11+62.05, 22.32' RT. TO STA. 12+75.48, 19.52' RT.									575
STA. 11+70.06, 23.69' LT. TO STA. 12+74.35, 23.98' LT.									526
STA. 12+71.96, 18.30' LT. TO STA. 13+11.64, 19.00' LT.			65						
STA. 12+77.26, 18.69' RT. TO STA. 13+08.41, 18.69' RT.			65						
STA. 12+93, LT.	63								
STA. 13+08.41, 18.69' RT. TO STA. 13+08.42, 37.95' RT.								24	
STA. 13+10.19, 24.63' LT. TO STA. 14+00.00, 18.95' LT.						95			
STA. 13+10.33, 18.60' RT. TO STA. 14+00.00, 18.60' RT.									445
STA. 13+10.74, 20.46' LT. TO STA. 14+00.00, 20.46' LT.									402
STA. 13+25, RT. TO STA. 14+00, RT.	144								
STA. 14+00, RT. TO STA. 14+36, RT.	88								
STA. 14+00.00, 18.95' LT. TO STA. 15+73.66, 19.12' LT.						176			
STA. 14+00.00, 18.95' LT. TO STA. 15+73.10, 19.62' RT.									741
STA. 14+00.00, 18.95' LT. TO STA. 15+78.08, 23.97' LT.									698
STA. 14+00.00, 13.00' LT. TO STA. 20+00.00, 13.00' LT.				258					
STA. 14+00.00, 13.00' RT. TO STA. 20+00.00, 13.00' RT.				122					
STA. 15+73.62, 16.68' LT. TO STA. 16+15.85, 16.64' LT.			68						
STA. 15+75.18, 13.67' RT. TO STA. 16+07.04, 13.90' RT.			72						
STA. 16+09.92, 20.39' LT. TO STA. 19+97.51, 28.37' LT.									1557
STA. 20+00.00, 13.00' LT. TO STA. 26+00.00, 12.00' LT.				151					
STA. 20+00.00, 13.00' RT. TO STA. 26+00.00, 12.00' RT.				93					
STA. 22+62.49, 13.27' LT. TO STA. 23+14.50, 14.04' LT.			50						
STA. 26+00.00, 12.00' LT. TO STA. 41+00.00, 12.00' LT.				167					
STA. 26+00.00, 12.00' RT. TO STA. 41+00.00, 12.00' RT.				167					
STA. 41+00.00, 12.00' LT. TO STA. 56+00.00, 12.00' LT.				167					
STA. 41+00.00, 12.00' RT. TO STA. 56+00.00, 12.00' RT.				167					
STA. 45+11.97, 33.90' LT. TO STA. 46+49.54, 25.72' LT.					206				
STA. 46+80.55, 25.69' LT. TO STA. 47+02.14, 29.42' LT.					20				
STA. 56+00.00, 12.00' LT. TO STA. 71+00.00, 12.00' LT.				167					
STA. 56+00.00, 12.00' RT. TO STA. 71+00.00, 12.00' RT.				167					
STA. 60+09.60, 70.00' RT. TO STA. 60+62.76, 33.94' RT.					120				
STA. 71+00.00, 12.00' LT. TO STA. 86+00.00, 12.00' LT.				167					
STA. 71+00.00, 12.00' RT. TO STA. 86+00.00, 12.00' RT.				167					
STA. 76+63.02, 28.60' RT. TO STA. 76+76.20, 22.12' RT.					13				

REVISIONS	
NAME	DATE
IDOT REVIEW	03/08
IDOT REVIEW	09/08

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

FAP 609 (IL RTE. 163)
SECTION 76RS-3, 76-2BR-2I
ST. CLAIR COUNTY

SCALE: VERT.
HORIZ.
DATE: 11/25/02

DRAWN BY: VERENSKI
DESIGNED BY: BOTT
CHECKED BY: EMRICK

GREENE & BRADFORD, INC.
OF SPRINGFIELD
CONSULTING ENGINEERS
3606 CONSTITUTION DRIVE
SPRINGFIELD, ILLINOIS 62707
(217) 793-9444

COMPUTER FILE NO.
SCHEDULE_V8
PROJECT: 02076
9/28/07 - MDS

IDOTPL50 1"=50' 8/24/98